



Research on Lean Management by BIM Technology in Shanghai Tower

Jin JIN

BIM Supervisor, Shanghai Tower Construction & Development Co., Ltd.



Agenda



Project Overview



Strategy Briefing



BIM Management Mode Selection by Owners



BIM Practice by Designers, Contractors and Supervisors




Reflections

Project Overview

- **Location**
 - Z3 lot, Lujiazui Fanatical Center
- **Section / Floor**
 - 9 sections, underground:5 floors, Ground : 121 floors
- **Building Height**
 - 632m
- **Construction Area**
 - 570,000 m² (0.16M underground, 0.41M ground)
- **Functional Orientation**
 - 24 hours opening International High Level office,
 - Super five-star hotel and ancillary facilities
 - Deluxe Shopping Mall
 - Tourism and Entertainment
 - Features Meeting Facilities





The height of Shanghai Tower is determined by full consideration of the other two skyscrapers in this area

Progress

Formally operation at middle of 2015

the end of
year



Project



Vertical Community

观光层 Observation Floors

- a. 高空景观
- b. 展览展示区
- c. 纪念品商店
- d. VIP餐厅
- e. 电梯厅



配套层 Amenity Floors

- a. 商业服务区
- b. 空中花园
- c. 办公区
- d. 电梯厅



High specification requirements
High specification standards
High Difficulty Issues

Observation Floors
Boutique Offices
Elevator & Restroom
Boutique Hotel
Amenity Floors
Amenity Floors
Typical Offices
Amenity Floors
Amenity Floors
Amenity Floors
Lobby&Retail& Conference center
Parking & Retail

地下停车场及零售区 Elevator Cabs & Restrooms

- a. 交通枢纽
- b. 设备区




Green Community



China Green Building:



LEED-CS2.0: Golden



BIM

Humanistic Community



Strategy Briefing

Issues

Too many sub contractors to coordinate

Hard to share the complex & huge information

Difficult to achieve cost control in such a big project

Difficult to achieve schedule control in such a long life-cycle project

Methodologies

Setup the team by organization behavioristic

Flexible operation system, using new tech: virtual construction, pre-fabrication, etc.

Blue Ocean Strategy: Value Innovation

Quantified Value Creation Comparative Analysis, Strategy selection Strategic positioning

Solutions

All staff participation & Specification Responsibility & Coordination Efficiency & Execution


**Design: BIM detailed design
Construction: factory precast
M&A: One-Stop service**

**Viable benefit allocation policy by BIM
low risk and high chance win-win model**

For Shanghai tower: Owner leading, contractors participating: Lean management by BIM


BIM Management Mode Selection by Owners

BIM features and usages



The bottleneck for the info technology adoption in building engineering is information sharing, and BIM is reliable solution for providing effective approaches of framing info sharing and management platform.

BIM Capacity Development





BIM Management Model: Options & analysis

Function & Effect	Scope	Effect	Adoption Level
BIM Adoption Mode			
Driven by Design Firm	Design Phase	in	wide
Driven By Contractor	Design Phase	in	new
Driven By Owner	Design Phase	in	a few


Owner Leading

All contractors participating

Lean Management Mode



Opportunity of BIM Application



US owner BIM ROI
McGraw-Hill Construction, 2009

Stanford CIFE center summarized huge gains and effects by BIM application according to 32 projects in US:

- 1) **Eliminates 40%** of the extra-budgetary changes
- 2) Time of cost estimation reduced **by 80%**;
- 3) The contract price reduced by **10%** (the average profit of the contractor in the past five years is **between 2.8% -3.3%** in China);
- 4) The duration of the project reduced by an average of **7%**.

Total construction area of 2010 was **7 billion** square meters, the finished area was **2.6 billion** square meters, **construction investment was 10 billion Yuan**. However, each 10,000 square meters of residential construction generated 500-600 tones of construction waste and accounted for 25% of municipal waste, the amount of dust accounted **for 22%** of the city.

With BIM adoption, cost estimation time can be cut off **by 80%**, **and 40%** of the budget changes can be eliminated .

(China Construction Research Institute, 2012 statistics)

Principle and strategy

Three Principles of Lean Management:

- **All staff participation & Specification**
- **Responsibility & Coordination**
- **Efficiency & Execution**

Shanghai Tower BIM Strategy Include:

What is the BIM Strategy Goal and how to Schedule it?

How to use BIM to increase ROI, accelerate growth?

How to Setup a qualified BIM Management Team?

How to Setup BIM Standard & Progress?

How to Manage & Coordinate all the designer contractor through contract terms

How to Examine BIM Adoption & Achievements?



Strategic Cooperation – Shanghai Tower & Autodesk




Shanghai Tower – Autodesk MOU Ceremony


2010.05.17




Software and technology framework in 2010



Software and technology framework in 2013




Lean management process




SC= Sub Contract
GC=General Contract
BC=BIM Consulting
SHT= Shanghai Tower

Goal with BIM



Organization framework



BIM Team Organization in Shanghai Tower

BIM Requirement in Tender Documentation

- ◆ BIM Requirement for Contractor
- ◆ BIM Requirement for Steel Subcontractor
- ◆ BIM Requirement for Elevator Subcontractor
- ◆ BIM Requirement for Curtain wall Subcontractor
- ◆ BIM Requirement for MEP Subcontractor
- ◆ BIM Requirement for Window-cleaning Equipment Subcontractor
- ◆ Etc.

机电分包工程建筑信息模型化（BIM）要求

- 分包商应负责在其服务范围内，并按业主及总包商要求，进行 BIM 模型化工作。
1. 基本要求
 - 1) 分包商应负责在服务范围内，进行 BIM 模型化工作。
 - 2) 分包商应建立完整的 BIM 模型，并应在项目开始 BIM 模型的创建前，向总包商提供 BIM 组织架构表和执行的 BIM 模型化工作。
 - 3) 分包商应指派专业人员进行 BIM 模型化工作，以保证 BIM 模型化工作的质量。
 - 4) 分包商应确保软硬件环境满足 BIM 模型化工作的要求。
 - 5) 分包商在服务期内，应提供与总包商 BIM 模型化工作相一致的 BIM 模型，同时向总包商提供 BIM 模型集成到总包商 BIM 模型的要求。
 - 6) 分包商提供的 BIM 模型，应符合总包商 BIM 模型化工作的要求。
 - 7) 分包商应提供所有 BIM 模型化工作的电子文件。
 - 8) 在项目结束时，分包商应提供 BIM 应用资料和相关文件。
 2. BIM 技术应用要求
 - 1) 通过 BIM 三维可视化技术，进行 BIM 模型化工作。
 - 2) 根据施工进度及时更新 BIM 模型，并应在施工过程中，进行 BIM 模型化工作的检测、报告。
 - 3) 基于 BIM 模型进行 BIM 模型化工作。
 - 4) 基于 BIM 模型及施工视频等文件，协调 BIM 模型化工作。
 3. BIM 模型要求
 - 1) BIM 模型应能用于定义各方工作界面，满足上海中心项目对模型文件的划分要求。
 - 2) BIM 模型文件应按项目要求合理命名。
 - 3) BIM 模型应包含机电工程中必要的构件，满足上海中心项目对模型构件的建模范围和详细程度的要求，并与项目实际情况保持一致。
 - 4) BIM 模型构件都应按专业附着不同的颜色，以便有效识别和区分。
 - 5) BIM 模型中的构件应能生成独立的参数化族文件，便于管理和各参与方的重复应用。
 - 6) 分包商应按照总包要求的模型格式来提交满足要求的 3D 模型。经过挑选的模型将会被整合，分包商将会在后继工作中被要求维护此模型的 BIM 完整属性。
 - 7) BIM 模型需合理组织和规划，确保能被各方应用。
 - 8) BIM 模型的构件信息应能满足后期运营维护阶段的数据管理应用。可参考《机电分包 BIM 模型运维信息要求》。业主和总包有权要求分包商根据项目实际情况随时增加相关信息。
 4. BIM 数据的所有权和权利

所有 BIM 模型以及所有其他项目过程中产生的数据都归属于业主所有。所有 3D、4D 和与 BIM 有关的信息均为保密信息。分包商在发布这些信息之前，应确保得到业主的同意和授权，并做好相关的数据传递/交接纪录。
 5. BIM 工作计划


分包商应提供 BIM 模型的创建、维护和应用计划，以及 BIM 人力资源计划，作为投标文件的组成部分。其中应至少包括以下几个时间节点的说明：

成果描述	完工时间
BIM 组织架构表	合同签订后的 10 天内
BIM 执行计划书	合同签订后的 20 天内
最初的 BIM 模型	合同签订后的 60 天内
施工深化图纸	与图纸一起递交 BIM 模型





Data Management Platform

Autodesk Vault




Set up Vault platform to ensure the Accuracy, Timeliness and Safety of data

- Data centralized management and distribution by Vault
- Through change order, auxiliary BIM for each process to ensure the process can proceed smoothly
- Record auditing information and data, for convenience of reviewing
- Remind users by email and working list



Data Management and Sharing by Vault



The data in Vault already surpassed 60G

上海中心 B

第二版

上海中心

20

1. 基础条款	2
1.1. 一般条款	2
1.2. 工作界面划分	2
1.3. 工作职责	2
2. 应用软件架构	4
2.1. 建模软件	4
2.2. 整合应用软件	4
2.3. 共享协同平台	4
3. 文件交换策略	6
3.1. 文件发布要求	6
3.2. 文件和文件夹命名方式	6
3.3. 文件更新	6
4. 模型分级	7
4.1. 模型分级原则	7
4.2. 几何精度分级	7
4.3. 信息分类	7
4.4. 模型级别表述	8
5. 工作流程最佳实践	9
5.1. 会议执行流程	9
5.2. 报告提交流程	9
5.3. 碰撞分析流程	10
5.4. 碰撞报告填写要求	11


Design Phrase

Visual Design

- 1) Improve by multi-discipline collaboration
- 2) Improve by visual design management



Parametric Design



data input
parameters input
conditions input

formula drive
data drive
scripts drive



data output
model output

share
analyze
feedback

model final
system selection


return

Sustainable Design




Light Pollution Analysis


Sustainable Design



Building wind environment simulation




Indoor natural lighting simulation




Underground natural lighting simulation

Construction phase

Improve construction management efficiency thru visualized simulation



Improve construction efficiency via multi-discipline collaboration



Construction schedule






Adjust construction plan via simulation, to avoid the potential collection, and to reduce the waiting. As the results, shorten the duration and reduce the cost

2 (model)

Shorten Construction Duration & Decrease Cost via BIM



Lean Fabrication and Construction

Improve the efficiency and reduce the cost in steel work thru pre-assemble simulation





Lean fabrication and construction with BIM model

Improve the efficiency and reduce the cost in steel work thru pre-assemble simulation





Lean Fabrication and Construction

**Curtain wall: Improve the efficiency of design and installation
thru pre-fabrication & pre-assemble simulation**



Lean fabrication and construction

MEP: Improve the efficiency and quality of design and prefabrication thru detailed design and pre- assemble simulation with BIM




Lean fabrication and construction

MEP: Improve the efficiency and quality of design and prefabrication thru detailed design and pre- assemble simulation)

Retrieve info via scanning code on ducts

物料信息	
物料编码	7#-4F-SA-1
物料类型	风管 (预制加工)
物料描述	铁梯门加工测试物料 规格 长: 1.5M 宽: 0.7M 高0.4M 7号楼预制加工件 吊装
生产信息	
生产厂商	上海市安装公司-预制工厂
生产日期	2012年12月17日
生产编码	S201250004 (2012年50周004号)
成品入库	2012年12月17日
成品出库	2012年12月28日
安装信息	
安装单位	上海市安装公司-第一分公司
到货日期	2012年12月28日
仓管员	林琪
领料安装日期	2013年1月7日
领料安装班组	风管班-1
内控检验日期	
内控检验	



Retrieve info of location ,properties & parameters, including installer, installation time




Retrieve electronic info from paper

Lean fabrication and construction

MEP: Improve the efficiency and quality of design and prefabrication thru detailed design and pre-assemble simulation


Benefits from Lan Prefabrication and construction plan :

- 1) 60% site work reduction
- 2) 90% reduction in hazard and poisonous work, ex. welding, glue, etc.)
- 3) 70% prefabrication of duct and pipe




Lean fabrication and construction

BIM for Decoration : improve quality and efficiency and reduce site work thru BIM model based design



Urinal unit



Displaced view of Urinal

Lean fabrication and construction


BIM for Decoration : improve quality and efficiency and reduce site work thru BIM model based design



BIM Model vs. On-site Installation Results

Quantity Take-off by BIM

- Architecture, Steel, MEP, Curtain wall, Decoration





清单
报告

零件号	截面	数量	材质	长度 (mm)	面积 (m2)	重量 (kg)
1P1	PL20*145	2	Q345B	240	0.1	5
1PH1002	PL6*30	6	Q345B	560	0.0	1
2QPJ1003	PL10*100	1	Q345B	1332	0.3	10
2QPJ1004	PL10*100	1	Q345B	1115	0.2	9
2QPJ1005	PL10*100	2	Q345B	1109	0.2	9
2QPJ1006	PL10*100	2	Q345B	873	0.2	7
2QPJ1007	PL10*100	2	Q345B	848	0.2	7
2QPJ1008	PL10*100	2	Q345B	594	0.1	5
2QPJ1009	PL24*1471	1	Q345B	3098	5.6	51
2QPJ1010	PL24*1249	2	Q345B	2456	3.9	35
2QPJ1011	PL24*1002	2	Q345B	1781	2.3	20
2QPJ1016	PL24*277	1	Q345B	530	0.3	28
2QPJ1018	PL24*277	1	Q345B	640	0.4	33
2QPJ1019	PL24*329	1	Q345B	640	0.5	40
2QPJ1020	PL24*277	1	Q345B	496	0.3	26
2QPJ1021	PL24*329	1	Q345B	496	0.4	31
2QPJ1028	PL30*130	9	Q345B	131	0.0	4
2QPJ1029	PL30*130	6	Q345B	221	0.1	7
3P1004	PL20*300	1	Q345B	1824	1.2	85
7P1245	PL8*95	1	Q345B	566	0.1	3
7P1307	PL8*114	1	Q345B	566	0.1	4
7P1345	PL10*95	3	Q345B	468	0.1	3
7P1392	PL30*143	9	Q345B	374	0.1	12
7P1538	PL10*261	1	Q345B	450	0.2	7
7P1553	PL25*138	2	Q345B	652	0.2	17
7P1624	PL12*140	1	Q345B	652	0.2	9
7P1627	PL12*140	1	Q345B	652	0.2	9


确认


- Info. lost from design model to QTO model
- Lack of QTO info. in design model
- Modeling rule difference
- etc.

Site monitoring via 3D laser scanning and BIM




Site monitoring via 3D laser scanning and BIM





Drawings to models




BIM Practice by Construction Supervisors

With BIM, supervision work extended to the design stage, construction preparation stage, construction stage and completion stage.

- Design stage – initial confirmation
- Construction preparation stage – intuitive understanding
- Construction stage – management of quality, schedule and safety
- Completion stage – model confirmation and information integration

OurBIM System

One platform
+
two sets of models
=
management
function



Schedule management: record

The screenshot displays the 'OurBIM上海中心工程管理系统' (OurBIM Shanghai Center Engineering Management System) interface. The main window shows a '进度明细表' (Progress Detail Table) for '幕墙墙工作记录' (Curtain Wall Work Record). The table lists 12 items, each with a sequence number, floor, location, and progress details. A pop-up window titled '工序详细信息' (Process Detail Information) is open, showing the process name '1~3次件安装' (1~3 times piece installation) and the acceptance time '2013-06-06'.

OurBIM上海中心工程管理系统

主菜单

个人办公 主页

我的主页

快捷入口

OurBIM上海中心工程管理系统

企业网站 | 企业邮箱 | 退出

主菜单

个人办公 主页 设施验收 进度明细表

幕墙墙工作记录

序号	楼层	部位	工序信息	操作
1	52层	外幕墙	查看详情	修改 定位模型
2	53层	外幕墙	查看详情	修改 定位模型
3	54层	外幕墙	查看详情	修改 定位模型
4	55层	外幕墙	查看详情	修改 定位模型
5	56层	外幕墙	查看详情	修改 定位模型
6	57层	外幕墙	查看详情	修改 定位模型
7	58层	外幕墙	查看详情	修改 定位模型
8	59层	外幕墙	查看详情	修改 定位模型
9	60层	外幕墙	查看详情	修改 定位模型
10	61层	外幕墙	查看详情	修改 定位模型
11	62层	外幕墙	查看详情	修改 定位模型
12	63层	外幕墙	查看详情	修改 定位模型

工序详细信息

工序名称 验收时间

1~3次件安装

单元板块安装 2013-06-06

总共 16 条 总共 2 页 当前第 1 页 每页 12 条

Copyright © 2013 JKSoft

Quality management: label

OurBIM上海中心工程管理系统

企业网站 | 企业邮箱 | 退出

主菜单

- 我的
- 主菜单
 - 我的主页
 - 现场管理
 - 质量管理
 - 质量问题明细表
 - 巡视检查
 - 过程验收
 - 未完成质量问题
 - 安全管理
 - 日常巡视
 - 专项检查
 - 设施验收
 - 进度管理
 - 进度明细表
 - 进度对比
 - 协调管理
- 模型索引图
- 监理文档系统
- 工程项目信息及权限

当前位置: 标签管理

专业: 幕墙 子类: 内幕墙 楼层: 56

生成月报 监理指令

序号	专业	子类	楼层	管理类型	标签人
1	幕墙	内幕墙	56	日常巡视	吴天华
2					吴天华
3					吴天华
4					吴天华

上海中心管理系统 - Internet Explorer, optimized for Bing and MSN

http://116.228.212.186:3380/JKPMWbs/Shzx/shzx_bz_list_info.aspx?id=119


※ 标签管理 > 详细信息

管理类型:	标注类型:	单点
专业: 幕墙	专业子类: 内幕墙	
内容信息: 检查中发现56层, 41层均有玻璃碰撞损坏	标签状态: 一般问题	
图片附件:		


Copyright © 2013 JKSoft

标签对应问题详细信息


Safety management: analysis



Operation phase



Asset management



风管隔热层 默认 [3327240] 关闭 >>

属性	值
ID	3295347.00
类型ID	589049.00
创建的阶段	86961.00
拆除的阶段	
设计选项	
系统缩写	
可用大小	630 mmx250 mm
总体大小	630 mmx250 mm
内衬厚度	
内衬类型	
隔热层厚度	
隔热层类型	
系统类型	3326309.00
系统分类	送风
系统名称	机械 送风 64
底部高程	3.15
顶部高程	3.40
尺寸	630x250
尺寸锁定	0.00
其他流量	0.00
水力直径	0.36
雷诺数	0.00
当量直径	0.42
剖面	
损耗系数	0.00
风压	0.00
面积	15.75
摩擦	0.00
压降	0.00
速度	0.00
直径	

BAS monitoring

10东1





标题

关闭

属性

值

产品名称

德国BOSCH监控摄像机



产品型号

博世 NDC-255-P

生产时间

2011年12月30日

安装时间

2012年03月10日

维修联系方式

021-33831489

采购价格

1600.51元

资产管理分类

安防设备

设备管理编号


SHTower-F10-02

权属单位



上海中心大厦建设发展有限公司

更多

Hazard monitoring




Access control and personnel management




姓名	时间
临时访客	2013-5-17 13:20:12
临时访客	2013-5-17 13:20:12
张三	2013-5-17 13:20:12
张三	2013-5-17 13:20:12
张三	2013-5-17 13:20:12
张三	2013-5-17 13:20:12
张三	2013-5-17 13:20:12
张三	2013-5-17 13:20:12
张三	2013-5-17 13:20:12
张三	2013-5-17 13:20:12
张三	2013-5-17 13:20:12

Fire extinguishing system management



Disaster warning and emergency response



Economic Indicator of BIM

**BIM economic indicators
(reference)**

ex.opening	unit cost of direct construction(CNY)
slab opening	2600
block opening	19800
block opening	5400
MEP opening	1600
total conflict	8400
total cost	10,000,000
average unit cost	1190.48

Analogy

**BIM economic indicator estimation of SHT
(by reference unit cost of conflict)**


area	unit
9F model floor	4656.1m ²
10F model floor	4648.4m ²
total area of model floor	9304.5m ²
total area of Shanghai tower	570000m ²
total conflict of model floor	1013
reference average cost	1190.48CNY
total cost of model floor	1,205,952.38CNY
total economic indicator cost of SHT	73,877,463.29CNY

BIM economic indicator estimation result of Shanghai tower (Cost per changes)

SHT Total	CNY 12 billion
Change rate	3%–5% in average
Fee subject to change	CNY 360 million)


Shanghai Tower save at least CNY 100 million with BIM adoption

Viable Benefit Allocation



Owner
Design Institute
Construction companies
Audit companies
Other

Establish reasonable reward tactics



Owner
Design Institute
Construction companies
Audit companies
Other

Reward the companies with the saved cost subject to new tech adoption, and put the statement inside the contract.

Reflections

1. The mode is decided by enterprise development strategies

- **Involve** lean BIM-based mode gradually into the company's management activities
- Shanghai Tower set up a structure to involve all parties
- Invited BIM consultants to take (as much as) advantages of BIM




2. Need to setup national BIM Implementation and related standards

- The overall BIM adoption in China is at the very primary stage
- Lacking of national-wide standards
- Lacking of mechanism for BIM adoption
- Suggest government set up unified BIM standards and promote BIM into real practices


Reflections

Real BIM Management by BIM Tec- How?





Science and Technology empower the new economy



An aerial photograph of the Shanghai skyline, featuring the Shanghai Tower, the Oriental Pearl Tower, and the Jin Mao Tower. The text "Thanks!" and "Suggestions & Advices" is overlaid in a large, bold, yellow font with a black outline.

Thanks!

Suggestions & Advices