

# Digital Construction With BIM 360

Steve Rudge – Excitech, Caroline Shaw – Balfour Beatty

Head of Construction, BIM Co-ordinator

Join the conversation #AUCity #AU2018





## About the Speaker

Steve Rudge - Excitech

Head of Construction – Project BIM Manager

BIM Manager – MECD Project (Balfour Beatty)



## About the Speaker

Caroline Shaw – Balfour Beatty

BIM Coordinator



# The MECD Project



## Digital Construction Using BIM 360

Project – Manchester Engineering Campus Development (MECD)

### Project description


- Costs in excess of £300 million
- More than 78,000m<sup>2</sup> (or 11 football pitches)
- Wide range of flexible hi-specification laboratories and lecture spaces
- A 'maker space' where students will see their engineering creations come to life.
- 1,300 academics, researchers and support staff will move to the new campus
- 6,750 students will be based at the new site





One of the largest construction projects undertaken by a Higher Education institution in the UK

## Building key

- |   |   |                                     |   |   |                                      |
|---|---|-------------------------------------|---|---|--------------------------------------|
| 1 Sackville Street Building                                   | 16 Manchester Interdisciplinary Biocentre - John Garside Building | 30 Precinct Shopping Centre         | 42 Martin Harris Centre for Music and Drama | 59 Simon Building                                 | 77 Ellen Wilkinson Building          |
| 2 Lambert Hall  | 17 George Begg Building   | 31 Crawford House                   | 43 Coupland Building 1                      | 60 Zochonis Building                              | 78 The Academy                       |
| 3 Fairfield Hall  | 18 Faraday Tower  | 32 St Peters House/Chaplaincy       | 44 The Manchester Museum                    | 61 Chemistry Building                             | 79 Stopford Building                 |
| 5 Chandos Hall  | 19 Faraday Building   | 33 Crawford House Lecture Theatres  | 45 Rutherford Building                      | 62 Dryden Street Nursery                          | 80 Horniman House                    |
| 7 Echoes Day Nursery  | 20 Ferranti Building  | 34 Prospect House                   | 46 Alan Turing Building                     | 63 Staff House Burlington Street                  | 81 The Manchester Incubator Building |
| 8 Renold Building   | 21 Maths and Social Sciences Building                             | 35 Humanities Bridgeford Street     | 47 Coupland Building 3                      | 65 Mansfield Cooper Building                      | 82 Whitworth Park Halls of Residence |
| 9 Barnes Wallis Building/Students' Union/Wright Robinson Hall | 22 Sugden Sports Centre   | 36 Arthur Lewis Building            | 48 John Owens Building                      | 66 Stephen Joseph Studio                          | 83 Grove House                       |
| 10 Vision Centre / Moffat Building                            | 23 Oddfellows Hall  | 37 University Place Visitors Centre | 49 Beyer Building                           | 67 Samuel Alexander Building                      | 84 The Whitworth Art Gallery         |
| 11 The Manchester Conference Centre and Weston Hall           | 24 Grosvenor Halls of Residences                                  | 37a University Place Hall           | 50 Whitworth Hall                           | 68 Students' Union Oxford Road (also at number 9) | 85 Opal Hall                         |
| 12 Pariser Building   | 25 Materials Science Centre                                       | 38 Waterloo Place                   | 51 Whitworth Building                       | 69 William Kay House                              | 86 Core Technology Facility          |
| 13 Staff House Sackville Street                               | 26 Manchester Business School East                                | 39 Kilburn Building                 | 52 Williamson Building                      | 70 Dover Street Building                          | 87 Denmark Building                  |
| 14 The Mill   | 27 Bowden Court   | 40 Information Technology Building  | 53 Roscoe Building                          | 71 Michael Smith Building                         | 88 Newman Building                   |
| 15 Morton Laboratory  | 28 Ronson Hall  | 41 Dental School and Hospital       | 54 Schuster Building                        | 72 Vaughan House                                  | 89 Lamb Building                     |
|   | 29 Manchester Business School West                                |                                     | 55 The John Rylands Library                 | 73 Avila House RC Chaplaincy                      | 91 McDougall Centre                  |
|   |   |                                     | 56 Schunck Building                         | 74 Holy Name Church                               |                                      |
|   |   |                                     | 57 Student Services Centre                  | 75 AV Hill Building                               |                                      |
|   |   |                                     | 58 Christie Building                        | 76 AQA  |                                      |







- School of Chemical Engineering and Analytical Science
- School of Electrical and Electronic Engineering
- School of Materials
- School of Mechanical, Aerospace and Civil Engineering
- Foundation Studies
- Dalton Nuclear Institute
- International Centre for Advanced Materials
- The Faculty Office
- Plus a range of centrally timetabled teaching spaces

## RIBA STAGE 6

HANDOVER

2020



## RIBA STAGE 5

CONSTRUCTION


2016 - 2020



## RIBA STAGE 4

TECHNICAL DESIGN

2013 - 2016



## RIBA STAGE 1-3

SCHEME AND INITIAL  
DESIGN


Back in 2012/2013






# The University Requirements

## The University Of Manchester



MANCHESTER  
1824  
The University of Manchester

EMPLOYERS INFORMATION REQUIREMENTS (EIR)




CLIENT:	UNIVERSITY OF MANCHESTER
PROJECT:	Manchester Engineering Campus Design (MECD)
PROJECT ADDRESS:	UNIVERSITY OF MANCHESTER ESTATES CAPITAL PROJECTS TEAM, G.003 BEYER BUILDING, OXFORD RD, MANCHESTER, M13 9PL
PROJECT STAGE:	STAGE 1 - PREPARATION
DOCUMENT NUMBER:	*****
REVISION:	2.0
STATUS:	FOR TENDERING INFORMATION ONLY
DATE:	OCTOBER 2013

Employer's Information Requirements for MECD

- Key Deliverables
- LOD Requirements
- Clash Management
- CDE Requirements
- Information Requirements (Space & Asset Management)


# Information Requirements





# Model Management


# The Design Team




Building Services



**NG Bailey**












**NG Bailey**

# Manchester Engineering Campus Development (MECD)






# Construction Model




# The Workflow






# Key Issues



- No Single Source Model (Risk)
- Collating Comments
- Approving Clashes
- Manual Model Federation
- Downloading large file to view
- Latest Version






# Construction Model





# Workflow For Approved Model Issue





Reducing Risk

Single source of truth

Saving:

15 hours a month – Model Federation

4 hours a month – Federating Comments

4 hours a month – Clash Reporting

276 Hours a year = around 36 days



# Reviewable Design Data (RDD) - Process

**Balfour Beatty**




Around 2000 Rooms




**excitech**

# RDD & WIP Model Distribution






# BIM 360 Document Manager



## CHANGES



15

Added

1

Removed

102

Modified

Disciplines affected

Modification type



Search + Filter

Flat Result List

Result as Tree

Basic Wall [11397131]

Basic Wall [11536198]

Basic Wall [12863549]


Basic Wall [13390573]

Basic Wall [14490460]

Basic Wall [14490461]

# BIM 360 Document Manager

Version 12 vs. Version 11



**INFORMATION**

### Basic Wall [11536198]

Changes between versions 12 & 11

Area by	-0.041 m <sup>2</sup>
Version 12	5.592 m <sup>2</sup>
Version 11	5.551 m <sup>2</sup>
Volume by	-0.005 m <sup>3</sup>
Version 12	0.693 m <sup>3</sup>
Version 11	0.688 m <sup>3</sup>

Moved by 0.1 ft in y  
Scaled by 1, 0.99, 1 on x, y, z

Show in model

Version 12 Version 11

**CHANGES**

0 of 15 Added 0 of 1 Removed 102 Modified

Disciplines affected Modification type

Search + Filter

Flat Result List Result as Tree


- Basic Wall [11397131]
- Basic Wall [11536198]
- Basic Wall [12863549]
- Basic Wall [13390573]
- Basic Wall [14490460]
- Basic Wall [14490461]

# BIM 360 Document Manager







# BIM 360 Document Manager



# BIM 360 Document Manager







### CHANGES

6  
Added

4  
Removed

Disciplines affected



Search + Filter

#### Flat Result List

Basic Wall [18989212]
Basic Wall [797896]
Basic Wall [808618]
BDP_Casework_Balustrade_void_free standing+handrail_900_module_2 [125]
BDP_Casework_Balustrade_void_free standing+handrail_900_module_2 [125]

### INFORMATION

<


Floor [1046701]

>


Changes between versions 1 & 6

Type Name to	BDP_Floor_Resin Paint_M12/FLH-301
Version 1	BDP_Floor_Resin Paint_M42/FLH-301
Version 6	BDP_Floor_Resin Paint_M12/FLH-301


Version 1



Version 6




# Not Just a Single Model







# Next Gen – Model Coordination



# Next Gen – Model Coordination

Search for documents

View

<input type="checkbox"/> Models	Contributor	Updated date ▾	
<input type="checkbox"/> 3D_5983-BDP-MCH-X-M3-A-20-81901.rvt		Today at 2:50 PM	12206
<input type="checkbox"/> 3D_5983-BDP-MECD-XX-M3-A-70-80901.rvt		Today at 2:07 PM	1106
<input checked="" type="checkbox"/> 3D_5983-BDP-YSB-X-M3-A-21-83902.rvt		Yesterday at 8:11 AM	310
<input type="checkbox"/> 3D_5983-BDP-MCH-X-M3-A-21-81902.rvt		May 3, 2018 5:25 PM	12174
<input type="checkbox"/> 3D_5983-BDP-OFH-X-M3-A-20-85901.rvt		May 3, 2018 5:24 PM	1875
<input type="checkbox"/> 3D_5983-BDP-UBS-X-M3-A-20-82901.rvt		May 3, 2018 5:21 PM	1532
<input type="checkbox"/> 3D_5983-BDP-OFE-X-M3-A-20-84901.rvt		May 3, 2018 5:21 PM	811
<input checked="" type="checkbox"/> 3D_5983-BDP-YSB-X-M3-A-20-83901.rvt		May 3, 2018 5:21 PM	594

# Next Gen – Model Coordination

⋮ Model Coordination

MODELS

CLASHES

19 models (2 hidden) ▾

Last updated Today at 3:16 PM

	3D_5983-BDP-ATH...20-88901_P20.rvt	3D_5983-BDP-MC...3-A-20-81901.rvt	3D_5983-BDP-MC...3-A-21-81902.rvt	3D_5983-BDP-ME...99-89903_P03.rvt	3D_5983-BDP-ME...3-A-70-80901.rvt	3D_5983-BDP-MEC...70-80901_P15.rvt	3D_5983-BDP-MEC...70-80901_P17.rvt	3D_5983-BDP-OF...3-A-20-84901.rvt	3D_5983-BDP-OF...20-84901_P29.rvt	3D_5983-BDP-OF...3-A-20-85901.rvt	3D_5983-BDP-OFH...20-85901_P30.rvt	3D_5983-BDP-UB...3-A-20-82901.rvt	3D_5983-BDP-UBS...20-82901_P32.rvt	3D_5983-BDP-UB...3-A-21-82902.rvt	3D_5983-BDP-UB...21-82902_P32.rvt	3D_5983-BDP-YS...3-A-20-83901.rvt	3D_5983-BDP-YS...20-83901_p32.rvt	3D_5983-BDP-YS...3-A-21-83902.rvt	3D_5983-BDP-YSB...-21-83902_P31.rvt
3D_5983-BDP-ATH-X...-A-20-88901_P20.rvt 0 clash groups																			
3D_5983-BDP-MCH-X-M3-A-20-81901.rvt 275 clash groups			83	22	140	157	144					13	13	1	1				
3D_5983-BDP-MCH-X-M3-A-21-81902.rvt 312 clash groups		287		17										8	8			3	1
3D_5983-BDP-MECD-X...-A-99-89903_P03.rvt 37 clash groups		22	7		4	4	4	1	1	1	1	3	3	1	1	1	1		
3D_5983-BDP-MECD-XX-M3-A-70-80901.rvt 1106 clash groups		628		4		481	388					140	140	3	3	10	10		





# Next Gen – Model Coordination

3D\_5983-BDP-MCH-X-M3-A-20-81901.rvt and 3D\_5983-BDP-MECD-XX-M3-A-70-80901\_P17.rvt

## 144 ELEMENTS WITH CLASHES

17 clashes with 1 other model

### Floor [1045178]

15 clashes with 1 other model

### Floor [6313139]

15 clashes with 1 other model

### Compound Ceiling [1111436]

14 clashes with 1 other model

### Compound Ceiling [1111353]

13 clashes with 1 other model

### Floor [1043007]

10 clashes with 1 other model

### Basic Wall [9311256]

8 clashes with 1 other model

### Basic Wall [819894]


7 clashes with 1 other model

### Floor [1045789]

7 clashes with 1 other model

### Floor [1036800]

6 clashes with 1 other model



# Field Management



- Live construction information available in the field
- Remove paper forms
- Improve QA/QC
- React to issues quickly
- Increase in productivity
- Central reports on performance





The image is a screenshot of the Autodesk BIM 360 Field Library Preview interface. At the top, the header displays 'AUTODESK® BIM 360™ FIELD' and 'CRMA0076 - MECD'. Below the header, a message says 'Thanks for trying the Library Preview' with a link to 'Exit preview'. A search bar is located on the left, and filters for 'All tags', 'All upload dates', and 'All locations' are on the right. The main content area shows a grid of document thumbnails. The first row includes 'Zone M General Arrangement Foundation...', 'Basement Wall Elevations and Sections S...', 'Service Mains and Ducting Details-19342...', and 'Monitoring Instrumentation Layout-'. The second row shows a site plan, 'Basement Wall Elevations and Sections S...', a structural grid, and a 'Feedback' button. The bottom left corner has a URL: 's://bim360field.autodesk.com/home'.

**excitech**

# BIM 360 Field Library Workflow

**Balfour Beatty**

## Information Extracted from Conject

File Name Breakdown 5983-ARP-MECD-EXG-SI-C-79-2XE01

Volume	Zones or Areas of the Build
Originator	Unique Identifier for each Organisation responsible for Creating Data
Element Code	Works in which the Information Relates to. Not all Element Codes to be Reflected. TBA

Information to be Pushed Through to BIM360 Field

ACC	Aquatic Centre Carpark
MCH	MEC Hall
USG	Upper Brook Street
YGB	York Street Building
OFH	Oddfellows Hall
JCR	James Chadwick Existing Refurbish
OFE	Oddfellows Extension (Models Only)
MECD	All Areas

Originator

UOM	University of Manchester
BB	Balfour Beatty
MEC	Mecanoo
ARP	Arup
PP	Phenotype Pressed
AEC	Aecom
SWE	Sweett
MLA	Mecanoo_Arup
EXC	Excitech
NGB	NG Bailey
EXP	Expanded
SPL	Sipral
SEV	Severnfield

## Information Reflected on BIM360 Field

Folder Structure Example

Volume
MCH – MEC Hall
Originator (TBA)
ARP - Arup
MEC - Mecanoo
NGB - NG Bailey
EXP - Expanded
SPL - Sipral
Element Code (TBA)
10 - Substructure
20 - Primary Structure - General
21 - External Walls
50 - Mechanical Services
52 - Drainage
60 - Electrical Services
62 - Power
63 - Lighting
67 - Fire Systems

Element Code

00 Site Plan	53 Hot & Cold Water, Domestic Water Services	67 Bar Loose Equipment
10 Substructure	54 Gas & Compressed Air	90 External Works - General
11 Ground Excavations	55 Refrigeration	91 Ground Preparation
13 Ground Bearing Slabs	56 Space Heating	92 Hard Landscaping
16 Retaining wall foundations	57 Ventilation & Air Conditioning	93 Soft Landscaping
17 Pile Foundations	58 Other piped, ducted services	94 Services
18 Other substructure elements	60 Electrical Services	95 Furniture & Fittings
20 Primary Structure - General	61 Electrical Supply	96 External Works - Service/Utilities General
21 External Walls	62 Power	97 Schedules
22 Internal Walls	63 Lighting	
23 Floors	64 Communications	
24 Stairs & Ramps	66 Transportation	
25 Auditorium	67 Fire Systems	
26 Sanitary Layouts	68 Security and Control Systems	
27 Roofs	69 Lightning Protection/Earthing	
28 Structural Frames	70 Fixed Furniture - General	
31 External Elements - Cladding	71 Signage Details	
32 Internal Elements - Joinery, Doors & Screens	72 Fixed Furniture Details	
33 Raised Floors	73 Kitchen Fitting Details	
34 Balustrades & Metalwork	75 Cleaning Fittings Details	
35 Suspended Ceilings	76 Storage & Shelving Details	
37 Roof Lights	77 Bar Fixture Details	
40 Details - General	78 Aquatic Centre Carpark	
42 Internal Wall Details	80 Loose Equipment - General	
43 Floor Finishes Details	81 Circulation Loose Equipment	
45 Ceiling Finishes	82 General Loose Equipment	
46 Sanitary Details	83 Kitchen Loose Equipment	
50 Mechanical Services	84 Sanitary Loose Equipment	
51 Combined M&E	85 Cleaning Loose Equipment	
52 Drainage	86 Storage Loose Equipment	

05/12/2016

1



**excitech**

# Problem – Monitor & Check Site Plant

**Balfour Beatty**



**excitech**



# Equipment Barcodes

**Expanded Plant**

**Excavator 2 Expanded**

**CAT320E**

**Supplier: SELECT**

Plant No: CAT0320ELNAZ00226



Excavator 2 Expanded

<input type="checkbox"/>	Excavator 1 Maher	Excavator 1 Maher	Excavator	CAT329EL	Off Hired
<input type="checkbox"/>	Excavator 4 Maher	Excavator 4 Maher	Excavator	Hitachi 2AXIS ZX470	Off Hired
<input type="checkbox"/>	Excavator 1 UDP	Excavator 1 UDP	Excavator	Hitachi ZX135US-5	Off Hired
<input type="checkbox"/>	Excavator 1 Expans	Excavator 1 Expans	Excavator	CAT312E	On Hire
<input type="checkbox"/>	Excavator 2 Balfour	Excavator 2 Balfour	Excavator	Excavator 2 Balfour Beatty	Off Hired
<input type="checkbox"/>	Excavator 2 Cummi	Excavator 2 Cummi	Excavator	Hitachi ZX135US-5	Off Hired
<input type="checkbox"/>	Excavator 2 Maher	Excavator 2 Maher	Excavator	Hitachi ZR330LC-5G	Off Hired
<input type="checkbox"/>	Excavator 6 Cummi	Excavator 6 Cummi	Excavator	Hitachi ZX225US-5	Off Hired
<input type="checkbox"/>	Excavator 10 Expar	Excavator 10 Expar	Excavator	Zaxis 5SU 5tne Excavator	On Hire
<input type="checkbox"/>	Excavator 1 Cummi	Excavator 1 Cummi	Excavator	Komatsu PC210LC-8	Off Hired
<input type="checkbox"/>	Excavator 4 Cummi	Excavator 4 Cummi	Excavator	Hitachi ZAXIS 225USLC-5B	Off Hired
<input type="checkbox"/>	Excavator 5 Expans	Excavator 5 Expans	Excavator	CAT 312E	Off Hired
<input type="checkbox"/>	Excavator 6 Expans	Excavator 6 Expans	Excavator	ZAXIS 52U	Off Hired
<input type="checkbox"/>	Excavator 7 Expans	Excavator 7 Expans	Excavator	Excavator 7 Expanded	Off Hired
<input type="checkbox"/>	Excavator 2 Expans	Excavator 2 Expans	Excavator	CAT320E	On Hire
<input type="checkbox"/>	Excavator 1 Balfour	Excavator 1 Balfour	Excavator	JCB - JS220LC	Off Hired
<input type="checkbox"/>	Excavator 3 Cummi	Excavator 3 Cummi	Excavator	Volvo ECR48C 5T	On Hire
<input type="checkbox"/>	Excavator 9 Expans	Excavator 9 Expans	Excavator	Excavator 9 Expanded - Long Reach	Off Hired
<input type="checkbox"/>	Excavator 4 Expans	Excavator 4 Expans	Excavator	Hitachi ZX225USL	Off Hired
<input type="checkbox"/>	Excavator 5 Cummi	Excavator 5 Cummi	Excavator	Komatsu PC170LC-10	On Hire

AUTODESK® BIM 360® FIELD CRMA0076 - MECD Equipment Excavator 1 Expanded

Back to Equipment

Checklists Issues Tasks Attachments Comments History

Attachments

File Library Library Preview Link Camera Download All

Plant & Equipment Specification Checklist\_360\_Tracked\_Excavator.pdf  
Added/Modified Aug 15, 2017 12:00 PM  
Public link

Plant.jpg  
Added/Modified May 25, 2017 8:53 AM  
Taken on May 9, 2017 11:26 AM  
Public link

Serial\_No.jpg  
Added/Modified May 25, 2017 8:53 AM  
Taken on May 9, 2017 11:26 AM  
Public link

Excavator\_Daily\_Checklist\_1.pdf  
Added/Modified May 25, 2017 8:54 AM  
Public link

Profile

Name  
Excavator 1 Expanded

Type  
Excavator

Description  
CAT312E

Location  
X

Status  
On Hire

Company  
Expanded

Identifiers

Barcode  
Excavator 1 Expanded

Serial number  
CAT0312ECPZL004774

Tag number

Asset ID

Submittal

Purchasing and Warranty

- All mobile & fixed plant items to be allocated an Individual barcode.
- Managing Hired Equipment and Plant
- Monitor plant duration and avoid missing plant items.
- Predefined report to identify the status of all the plant on site.





- Waterproof permit on a high visibility armband in order to recognise who the permit has been issued to onsite/space.
- Provides a clear identification of who has been issued the permit on site.
- A manager can carry out a spot check using the QR Code Scanner to ensure the permit is in date and is being used in the correct location.
- Check anyone issued a permit has received adequate training and is considered competent to carry out operation.
- All related check sheets and photos are appended to a particular permit on a daily basis.

# Permits Issued on Site

**Balfour Beatty**





# Problem – Supply Chain

(Ops/Const. & HSEQ)

temporary works

Deck Control Sheet

Slab Construction Control Sheet for Falsework

No activity is to be executed out of sequence  
No activity to be commenced prior to sign off by responsible person of the previous activity

Block: South Basement Level: Ground Floor

Item	Activity	Responsible	Action Complete	
1	Drawing issued Consultation Temporary works coordinator (TWC)/Charge Hand (CH) joiner. Review and discuss scheme, raise issues prior to commencing work. Drawings to be amended and signed off	Temporary Works Co-ordinator (TWC)/CM & Foreman		
2	Deck Erection Plan Decking erection plan is developed, discussed, agreed, & understood by Foreman responsible for works.	CM/TWC & Foreman		
3	Fall Restraint/Arrest Protection Systems Fall restraint layouts established. Infill and leading edges clearly identified. <b>DECK CONSTRUCTION MAY COMMENCE</b>	Foreman		
4	Deck construction is complete (If part of the deck is completed sign-off as required)	Foreman	1	2
			3	4
5	Complete any missing Edge protection Inspection of working platform	Foreman Scaffolder		
6	Deck and Working Platform are safe for the following trades: e.g. Installation of store, ender, rebar, PT, etc. Leading edge works fully complete <b>TRADES MAY COMMENCE WORK</b>	CM/TWC		
7	Issue permit to load <b>CONCRETE MAY BE PLACED</b>	TWC		
8	Slab Edge protection is complete Install temporary handrail system to slab edges	TWC		
9	Issue permit to unload (If part of the deck is to be unloaded sign-off as required)	TWC	1.	2.

02-UK 4G 12:44 44%

Checklists Find Checklists Acceptance of Panel Workmanship Checklist

Stillage No enter text

Issue Tap to enter comments

Unique Panel No enter text

Issue Tap to enter comments

Activity Acceptance of Panel Tap to enter comments

Issue Tap to enter comments

Panel Ref enter text

Issue Tap to enter comments

Panel destination (GL/Level) Choose Date

Issue Tap to enter comments

1 Stillage arrived secured in Lorry Yes No N

Issue Tap to enter comments


2 No visible damage to packaging Yes No N

AUTODESK® BIM 360™ FIELD

# Expanded Concrete Elements

- Engaged with Expanded to develop check sheets
- Concrete Elements listed as a piece of equipment
- Relevant check sheet appended to relevant concrete equipment
- Progress Mark Ups







# Equipment Barcodes – Check Sheets











# Sipral – Façade

- Track & Trace
- Barcode Utilisation – Panel Ref & Type
- Logistics Status of Panel and Stillage
- Associated Check Sheets
- Generic & Bespoke Panel Location
- Location Allocation
- Appearance Profile – Utilising Status Code Allocation




# BIM 360 Field – Progress Tracking




		Date Created	Scheduled For		
   AUTODESK® BIM 360™ FIELD	 	15 Jan 2018 10:32 AM		 	
		23 Nov 2017 8:36 AM	28 Nov 2017 9:00 AM		
		12 Apr 2018 1:45 PM	13 Apr 2018 2:00 PM		
		12 Apr 2018 3:14 PM	13 Apr 2018 9:00 AM		
		17 Jan 2018 10:21 AM	19 Jan 2018 3:00 PM		
		15 Jan 2018 10:32 AM			
		15 Jan 2018 10:32 AM			
		17 Jan 2018 10:17 AM	18 Jan 2018 9:00 AM		
		05 Apr 2018 10:23 AM	05 Apr 2018 9:00 AM		
		18 Apr 2018 11:43 AM	18 Apr 2018 9:00 AM		

## EQUIPMENT





# Appearance Profile




# Navigation View Points

- Providing viewpoints within the model around the MECD site
- Barcode Mapped into BIM 360 Field as Equipment



# Site Navigation Points










# Dynamo Script – Within Revit

**Balfour Beatty**



**excitech**





- Provide Site Team Access to Live Design Information
- 2D & 3D Data
- Printing Facilities
- Information Hub for Site Briefings



# Information Requirements


# Information Requirements

[illegible]




# Space Management

**Balfour Beatty**



**excitech**

# Asset management




# Information Requirements

Pr_65_57	65	57				<b>Filter products</b>			
Pr_65_57_02	65	57	02			<b>Air filters</b>	-	-	-
Pr_65_57_02_02	65	57	02	02	AFI	Activated carbon air filters	NO	-	-
Pr_65_57_02_07	65	57	02	07	AFI	Bag air filters	NO	-	-
Pr_65_57_02_29	65	57	02	29	AFI	Fabric filters	NO	-	-
Pr_65_57_02_37	65	57	02	37	AFI	High efficiency particle arrestor (HEPA) air filters	NO	-	-
Pr_65_57_02_52	65	57	02	52	AFI	Mesh air filters	NO	-	-
Pr_65_57_02_66	65	57	02	66	AFI	Panel air filters	NO	-	-
Pr_65_57_33	65	57	33			<b>Gas and air filters</b>	-	-	-
Pr_65_57_33_02	65	57	33	02	AFI	Activated carbon compressed air filters	NO	-	-
Pr_65_57_33_15	65	57	33	15	AFI	Coalescing compressed air filters	NO	-	-
Pr_65_57_33_25	65	57	33	25	AFI	Dust compressed air filters	NO	-	-
Pr_65_57_33_33	65	57	33	33	GFI	Gas filters	NO	-	-
Pr_65_57_96	65	57	96			<b>Water filters and strainers</b>	-	-	-
Pr_65_57_96_08	65	57	96	08	STR	Basket water strainers	YES	300/350	YES
Pr_65_57_96_13	65	57	96	13	WFI	Chlorine dioxide biological water filters	YES	300/350	YES
Pr_65_57_96_77	65	57	96	77	WFI	Side stream water filters	YES	300/350	YES
Pr_65_57_96_99	65	57	96	99	STR	Y-type water strainers	YES	300/350	YES
Pr_65_65	65	65				<b>Ductwork products</b>			
Pr_65_65_23	65	65	23			<b>Ductwork accessories</b>	-	-	-
Pr_65_65_23_01	65	65	23	01	DAP	Access panels	YES	100	NO



# Information Capture



(00)123456789101112133

O2-UK 4G14:1843%

< Equipment

Column C0234

Details

Checklists

Issues

Attachments

Activity

Tasks

Profile

Identifiers

Barcode

Serial number

Tag number

Asset ID

Submittal

Purchasing and Warranty

Purchase order

Purchase date

Install date

AUTODESK® BIM 360™ FIELD

- Information Captured at Source
- Information direct to asset
- Links back to the model
- Single source of truth
- Aid the O&M data capture



# Information Verification



Geometry  
Information



Building Fabric															
Element	Sub Element	UoM Barcode Required	Asset Group	Ref Revit File											
Responsibility		UoM	Asset		Design team	Design team/ UoM	Design team	Design team	Design team	UoM	Contractor	Contractor	Contractor	Contractor	Contractor
Design		4	4		4	4	4	4	4	5	5	5	5	5	5
Safety Systems															
Safety Systems	Window Cleaning Access System		BVCS	Excel											
Safety Systems	Roof Anchorage Points		BRAP												
Safety Systems	Abrail rope		BABS												
Safety Systems	EdgeBolt		BEYE												
Safety Systems	Load limit / Impact resistance capacity		BS1078												
Safety Systems	Connectors		BCON	NOT MODELLLED											
Safety Systems	Energy Absorbing Linings		REAL	NOT MODELLLED											
Safety Systems	EdgeBolt and/or Personal Fall Protection		BEYF												
Safety Systems	Mobile Man Anchors		BMAA												
Safety Systems	Retractable Fall Arrestor		BIFA	NOT MODELLLED											
Doors															
Doors	Fire Door		BFDR												
Doors	Roller Shutter		RRLS												
Doors	Sliding Door (standard rated)		BSDR												

# Model Audit

## BIM Interoperability Tools – Model Checker

The screenshot shows a software window titled "Element Checks Organized by UniFormat | Report". The window has a toolbar with icons for "Export HTML", "Copy to Clipboard", "Expand All", "Collapse All", "Cancel", and "Help". Below the toolbar is a header bar with the title "Element Checks Organized by UniFormat Check Report". The main content area is divided into two sections: "Overall Result" and "Check Data".

**Overall Result:** 83% (39/47 PASS)

**Check Data:**


- Revit File: USACE-Revit-Model-Checker-Sample-Project-2017.rvt
- Full Path: C:\Users\j... \Desktop\USACE-Revit-Model-Checker-Sample-Project-2017.rvt
- Date: Wednesday, December 14, 2016 - 12:54:46 PM
- Config File: [https://www.biminteroperabilitytools.com/modelchecker/downloads/Element Checks Organized by UniForma...](https://www.biminteroperabilitytools.com/modelchecker/downloads/Element%20Checks%20Organized%20by%20UniForma...)

**Report Detail:**

- Element Checks Organized by UniFormat
  - PASS A1010.10 - Wall Foundations
  - FAIL A1010.30 - Column Foundations
    - Failures by Type Failure Count: 56 Total
  - FAIL A4020 - Structural Slabs-on-Grade
    - Failures by Type Failure Count: 2 Total
  - PASS B1010.10 - Floor Structural Frame
  - PASS B1010.20 - Floor Decks, Slabs, and Topping

# Virtual Build Meeting

**Balfour Beatty**



**excitech**



# Construction Fails

**Balfour Beatty**



**excitech**

Change! Not first come, first served


**Balfour Beatty**



**excitech**



# Accuracy – More and More Important







Change! Not first come, first served



# Step 1: Load The Design Model into Navisworks




# Step 1: Align The Point Cloud To The Model






# Step 1: Select The Objects To Be Analysed





# Step 2: Analyse in Verity



# Capture Issues Early

Balfour Beatty





# Step 3: QA/QC Objects in Verity

The screenshot displays the Verity software interface. The left pane shows a 3D model of a building structure with a blue vertical element highlighted. The right pane shows a 3D point cloud model of the same structure. A blue callout box points to the 'UC-Universal ...' entry in the table, with the text: "Or by selecting it from the element analysis table in Verity."

Verity 1.0 SP2 - AMB - Verity Analysis June 2017 - VAn001\_2017.08.24

Host: [Icons]

Auto-Zoom: ☒ Inspection Mode: ☐

Analyze: [Buttons]

Visibility: ☒ Designed Solid, ☒ Designed Wireframe, ☒ As-Built Solid, ☒ As-Built Wireframe, ☒ Points

Point Color: Single Point Color

Heatmap: None

Opacity: 50 (Designed), 50 (As-Built), 100 (Points)

Camera: ☒ Lock Z, ☒ Orthographic

QA Tools: [Icons]

Reft: [Buttons]

Item Description	Geometry Surface Area	Installation Status	Item Tolerance	Conformance To Tolerance	Review	Review Status	Action Required	Notes
33666-FLR-RGB-REG-REV/...	16,698,671.119 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		
UC-Universal ...	13,728,932.542 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		
33666-FLR-RGB-REG-REV/...	16,698,671.119 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		
UC-Universal ...	13,728,932.542 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		
33666-FLR-RGB-REG-REV/...	13,728,932.542 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		
UC-Universal ...	13,728,932.542 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		
UC-Universal ...	13,728,932.542 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		
UC-Universal ...	16,698,671.119 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		
UC-Universal ...	13,728,932.542 mm²	Installed	12,700 mm	Out Of Tolerance		Not Reviewed		

# BIM 360 Field – Field Verification

It isn't possible to laser scan everywhere

- Time
- Cost
- Access





# Verification

**Balfour Beatty**





**excitech**



# Benefits



# Analytics - Dashboards



# Key Points

- Get the Project team buy in
- Work as a team
- Listen to the problems and look for solutions
- Don't be afraid of change
- Define and document the procedures





# Statements

**Balfour Beatty**

## Alex Wyman – Section Engineer

BIM Field has enabled me to **proactively manage QA on site**. With the ability to **access all of the check sheets**, specifications and drawings, and also take photographs as part of pre pours and post pours to provide evidence of compliance for the client and link them to it has streamlined the process and enabled us to **provide a much higher standard of Quality Assurance** to the client than I have been able to provide in the past.

## Naran Vekaria – Quality Manager

Initial I was optimistic about using BIM 360 Field, thought it was a another tool and was a hindrance.

But more I got to use the BIM 360 Field I found it to be more part of me as **handy information reference** and easier to **raise observations** while on site.

## Andrew Tunley – Section Engineer

I think the key is to having the system **set up right in the beginning** and having the support of someone running with it to maintain and **keep up the quality**.

As you may tell if done right then this **can save a vast amount of time** and also on the environment it **reduces the amount of paper** used just as a check.

Also with pictures tagged to correct locations and none missed this also helps as a **quality check** as well.

Last words.... **Stress reduced, more time to concentrate on site safety** and looking after others as part of my Mental Health First Aid.

## Stephen Gilcrest - Trainee Site Manager

BIM 360 field in my opinion has many benefits overall that not only provides assistance on site but keeps records of all documents carried out, **minimising paper copies** that can be well controlled, organised and **improve the quality assurance** for every aspect throughout this project.

I believe this will help towards improving management professionalism on site **reducing time spent in the office** having information to access and manage in the field when needed, that could **potentially save on cost overall**. While using this system many other programmes on the main Autodesk website can be filtered down to assist managers on site, checking outstanding items which help me personally to keep track and close items I have raised. I would **provide reports** based on items/issues that need resolving emailing subcontractors making them aware to resolve/close out. I think this is improving project performance on MECD and will **help achieve minimal defects/snags** towards handover date making Balfour Beatty more efficient.



**excitech**

# Summary

## AUTODESK® BIM 360™ DOCS

- To Replace the Arup FTP Site
- To Share WIP Models
- Compare File Versions

## AUTODESK® BIM 360™ GLUE

- To view and navigate around project models on site with an iPad
- Raise Comments and Mark Ups directed at the BB design team
- Host Navis File
- Link Equipment Sets to BIM 360 Field
- Link Room Barcodes to BIM 360 Field
- Verification For As Constructed Model

## AUTODESK® BIM 360™ FIELD

- Daily Diaries
- Construction Approved Document & Drawing Library
- QA Check Sheets
- H&S Check Sheets
- Observations; Supervisor, Site Operatives, Consultant
- Plant Tagging & Register
- Site Permits; Hot Works Permit, Permit to Dig
- Location Barcodes to collate information against a location
- Verification For As Constructed Model

## AUTODESK NAVISWORKS

- BB Clash Management
- Viewing the BIM 360 Glue Model (BIM 360 Tab)



Autodesk and the Autodesk logo are registered trademarks or trademarks of Autodesk, Inc., and/or its subsidiaries and/or affiliates in the USA and/or other countries. All other brand names, product names, or trademarks belong to their respective holders. Autodesk reserves the right to alter product and services offerings, and specifications and pricing at any time without notice, and is not responsible for typographical or graphical errors that may appear in this document.

© 2018 Autodesk. All rights reserved.

