



Baptist MD Anderson
Cancer Center



FAU Schmidt Family
Complex



UCSF Block 23A
Neurosciences Research
Building



Discovery Meadows Child
Development Center



DPR | Reston Office
Tenant Improvement



Clemson University Allen
N. Reeves Football
Complex



Digital Realty 907 Security
Row Data Center



QTS Data Center 1, Phase
I



University of San Diego
Beyster Institute for
Nursing Research



Banner Boswell Medical
Center Hybrid Operating
Room



Colorado Tower



UCSF Medical Center at
Mission Bay



CyrusOne Building 4 Data
Center, Phase 1



DPR Construction Net-Zero
Energy San Francisco
Regional Office



Sutter Health Eden
Medical Center



Workday - Atlanta Office
Buildout



Mayo Clinic West
Expansion Tower



USPI West Palm Beach
Medical Office Building



Morehouse School of
Medicine | Billye Suber
Aaron Pavilion



Crosstown Center Phase II



Founded
1990

Privately held, employee owned

Collaborative, open-office
environment

Culture of discipline

Specialize in technically challenging
and sustainable projects

National and targeted international
experience

GOAL for VDC at DPR

MISSION STATEMENT:

Virtual Design & Construction (VDC)

Is focused on **integrating** the use of the building information model (BIM) to **improve our everyday processes for project delivery...** beyond design coordination.

DPR Construction is working to fully **implement VDC** on our projects to help our teams deliver projects **more efficiently**, in order to provide **more predictable** results to our clients while elevating the job satisfaction of our teams.



VDC vs BIM

*Virtual Design & Construction is about using the BIM to improve the building process **through a visual medium**.*


*VDC is more than just having a BIM model, it's about combining people, process and tools **to better execute work**.*



VDC Self Perform Work Process

From Design to Production

- **Defining scope of Self Perform Work**
- **Model coordination**
 - Vconstruct assists with SPW scope model creation
- **Creating production drawings**
 - Production drawings are given a unique name or number that is used to identify, quantify and track the scopes through the entire process.
- **QC review**
- **Approved production set**



Richmond Project


- \$600M
- 24 MONTHS
- 107MI OF STRUT
- 157K FITTINGS
- 450K BOLTS
- 28,289 LF OF FRAMING
- 930,453 SF OF DRYWALL
- 622 DOORS



Project Expectations

How we measure success

- Prefabrication
- Order setup
- Inventory Tracking
- Supplier Issues log
- High level visuals
- Production Tracking
- Status Tracking



Prefabrication

Benefits of this approach

- Reduced coordination with other trades
- Early installation/reduced schedule risk
- Comprehensive and complete execution of design using jigs
- Consistent quality control using standardized methods and practices
- Increased on-site efficiency
- Reduced manpower




Overhead Unistrut Structure


Prefabrication Cycle

- VDC
- Production
- Manufacturing
- Install


Virtual Design




Production Design



Manufactured Module





Module Install



Overhead Unistrut Grid


Coordinating the Strut

- Creating Parts
- Material list
- Prefabrication
- Jigs
- Shipments
- Field install



Unistrut Module

ITEM	ITEM QTY	PART NUMBER	TYP-Aisle	DESCRIPTION	APPEARANCE
1	18	1/2" e x 3'		Threaded Rod	Default
2	62	A-306		3 Hole, 90° Fitting	Steel Galvanized
4	2	A-326-2		6 Hole Double Corner Conn	Steel Galvanized
5	6	A-327-2		8 Hole Double Wing Conn	Steel Galvanized
6	602	ANSI B18.2.1 - 1/2-13 UNC - 0.75		Hex Cap Screw	Semi-Polished
7	34	ANSI B18.2.2 - 1/2 - 13		Hex Nuts (Inch Series) Hex Nut	Semi-Polished
8	2	B-605		Four Hole Splice Clevis	Steel Galvanized
9	34	F-201		1/2 Square Washer	Default
10	2	F-204-4		4 Hole Connecting Plate	Steel Galvanized
11	8	F-207		3 Hole Swivel Plate	Steel Galvanized
12	4	F-210		3 Hole, Flat Angle Plate	Steel Galvanized
13	13	F-213		4 Hole, T Plate Fitting	Steel Galvanized
14	4	F-214		4 Hole Corner Conn Plate	Steel Galvanized
15	13	F-216		5 Hole Cross Plate	Steel Galvanized
16	18	F-217		4 Hole, T Flat Plate Fitting	Steel Galvanized
17	2	H-132 x 20'		12 Ga Strut - Solid	
18	8	H-132 x 4'-5 1/2"		12 Ga Strut - Solid	
19	2	H-132 x 8'-7/8"		12 Ga Strut - Solid	
20	5	H-132-A x 11'-10 3/8"		Back to Back Strut - Solid	
21	2	H-132-A x 20'		Back to Back Strut - Solid	
22	1	H-132-A x 3'-9 5/8"		Back to Back Strut - Solid	
23	14	H-132-A x 5'-5"		Back to Back Strut - Solid	
24	3	H-132-A x 7'-10 3/8"		Back to Back Strut - Solid	
25	2	H-132-A x 9'-7/8"		Back to Back Strut - Solid	
26	2	H-132-A-CA3 x 5'-5"		3 PCS Welded BK to BK 12Ga Strut Solid	
27	2	H-132-OS x 11'-7 1/8"		12 Ga Strut - Slotted	
28	12	H-132-OS x 2'-10 5/8"		12 Ga Strut - Slotted	
29	2	H-132-OS x 20'		12 Ga Strut - Slotted	
30	2	H-132-OS x 3'-10 3/8"		12 Ga Strut - Slotted	
31	4	H-132-OS x 4'-1/2"		12 Ga Strut - Slotted	
32	2	H-132-OS x 7'-9 5/8"		12 Ga Strut - Slotted	
33	8	H-132-OSA x 11'-7 1/8"		Back to Back Strut - Slotted	
34	602	N-803		1/2-13 Nut-No Spring	Steel Galvanized
35	2	F205		4 Hole Splice Plate	Steel Galvanized
66	16	HC-208-3		3 Hole Hinge Connector	Default
85	6	A-326-9		9 Hole Triple Wing Conn	Steel Galvanized
67	8	H-132A x 3' 10-3/8"		Back to Back Strut - Solid	
68	8	H-132 x 3' 10-3/8"		12 Ga Strut - Solid	
69	8	H-132 x 3'-5"		12 Ga Strut - Solid	



Cut Optimization

Waste Reduction

- Cut Optimization
- Identifying waste
- Results

Stocks		Used Qty:	2762								
		Unused Qty:	69438								
		Layout Qty:	42								
Parts		Cut Parts:	6525								
		Uncut Part:	0								
Stock ID	Stock Length	Material	Qty	Layout No.	Cut Parts	Offcut Length	Utilization, %	Cost			
5	20'	H-132 - Ct	496	32	1		100	\$22.00			
4	20'	H-132 - A	134	12	1		100	\$56.20			
1	20'	H-132	176	1	1		100	\$22.00			
1	20'	H-132 - A	4	2	2		100	\$22.00			
2	22'	H-132 - A	2	9	3		99.76	\$56.20			
5	20'	H-132 - Ct	4	33	2 1 1/8"		99.53	\$22.00			
4	20'	H-132 - A	14	13	1 1 5/8"		99.32	\$56.20			
4	20'	H-132 - A	1	14	4 2"		99.17	\$56.20			
7	20'	H-132 - Ct	30	41	2 3 1/8"		98.7	\$56.20			
4	20'	H-132 - A	18	15	2 3 1/2"		98.54	\$56.20			
8	22'	H-132 - A	70	31	4 4"		98.48	\$168.84			
1	20'	H-132	3	3	4 4"		98.33	\$22.00			
5	20'	H-132 - Ct	160	34	5 4 1/4"		98.23	\$22.00			
5	20'	H-132 - Ct	104	35	4 5 3/4"		97.6	\$22.00			
1	20'	H-132	56	4	4 6"		97.5	\$22.00			
4	20'	H-132 - A	15	16	4 7 5/8"		96.82	\$56.20			
4	20'	H-132 - A	4	18	3 8 1/8"		96.61	\$56.20			
6	12'	H-132 - Ct	216	42	1 4 7/8"		96.61	\$13.20			
4	20'	H-132 - A	2	17	5 8 1/8"		96.61	\$56.20			
4	20'	H-132 - A	62	19	5 8 1/4"		96.56	\$56.20			
5	20'	H-132 - Ct	1	36	5 9 3/4"		95.94	\$22.00			
5	20'	H-132 - Ct	4	37	2 10 1/8"		95.78	\$22.00			
5	20'	H-132 - Ct	48	38	3 11 5/8"		95.16	\$22.00			
2	22'	H-132 - A	8	10	3 1 1 7/8"		94.74	\$56.20			
1	20'	H-132	140	5	5 1 7/8"		94.64	\$22.00			
5	20'	H-132 - Ct	9	39	8 1 2 1/4"		94.06	\$22.00			
2	22'	H-132 - A	8	11	4 1 4"		93.94	\$56.20			
4	20'	H-132 - A	228	20	3 1 3 5/8"		93.49	\$56.20			
4	20'	H-132 - A	28	21	2 1 6 1/8"		92.45	\$56.20			
4	20'	H-132 - A	18	22	2 1 7 5/8"		91.82	\$56.20			
1	20'	H-132	30	6	2 1 9"		91.25	\$22.00			
4	20'	H-132 - A	8	23	1 2 3/4"		89.69	\$56.20			
4	20'	H-132 - A	11	24	1 2 7/8"		89.64	\$56.20			
1	20'	H-132	265	7	2 2 2 1/4"		89.06	\$22.00			
4	20'	H-132 - A	4	25	2 2 7 3/4"		86.77	\$56.20			
4	20'	H-132 - A	260	26	2 2 8 5/8"		86.41	\$56.20			
4	20'	H-132 - A	2	27	4 3 5/8"		84.74	\$56.20			
4	20'	H-132 - A	17	28	2 3 2 1/8"		84.11	\$56.20			
4	20'	H-132 - A	1	29	2 3 2 1/4"		84.06	\$56.20			
4	20'	H-132 - A	83	30	3 3 2 3/8"		84.01	\$56.20			
1	20'	H-132	15	8	3 3 3"		83.75	\$22.00			
5	20'	H-132 - Ct	1	40	5 6 1/4"		69.9	\$22.00			
Utilization, %:		94.98									
Total Cost:		\$101,888.00									



Building 1

MDF A

Stock Info

Qty: 2
 Length: 20'
 Cost: \$44.00
 Usage, %: 82.71
 Waste, %: 17.29
 Offcut Length: 3' 5 1/2"
 Material/Type: H-132

Page: 1D_2

Cuts Info


Cut No. 1 2 3 4
 Cut Location 4' 1 5/8" 8' 3 1/4" 12' 4 7/8" 16' 6 1/2"

Qty: 2

4' 1 5/8"	4' 1 5/8"	4' 1 5/8"	4' 1 5/8"	3' 5 1/2"
MDF - 15	MDF - 15	MDF - 15	MDF - 15	

Stock ID	Part ID	Length	Location
1	MDF - 15	4' 1 5/8"	
1	MDF - 15	4' 1 5/8"	4' 1 5/8"
1	MDF - 15	4' 1 5/8"	8' 3 1/4"
1	MDF - 15	4' 1 5/8"	12' 4 7/8"

Overhead Unistrut Layout (OVERALL)



Unistrut and Module Schedule-1D1				
Item #	Count	Type	Comments	Element Length
46	6	Aisle		
6	2	Aisle Protected		
2	2	Aisle Protected_L		
2	2	Aisle Protected_R		
2	2	Wall		
32	208	H132A	Grid/Infill	3'-10 3/8"
50	30	H132A	Grid/Infill	5'-10 1/2"
53	30	H132A	Grid/Infill	6'-10 3/4"
65	28	H132A	Grid/Infill	7'-10 7/8"
72	28	H132A	Grid/Infill	8'-8 3/4"
65	16	H132A	Grid/Infill	8'-11"
72	16	H132A	Grid/Infill	9'-8 7/8"
74	8	H132A	Grid/Infill	10'-2"
78	16	H132A	Grid/Infill	12'-5"
101	8	H132A	Grid/Infill	17'-10 1/4"
110	28	H132A	Grid/Infill	19'-10 3/8"
115	1	H132A	Grid/Infill	21'-10 5/8"
117	1	H132A	Grid/Infill	84'-6 5/8"
367	1	H132A	Wall Mount	152'-8"
119	1	H132A	Grid/Infill	152'-9 3/8"
9	31	H132-OS	Grid/Infill	10'-1 3/8"
22	2	H132-OS	Grid/Infill	250'-6 3/4"
1	268	H132-OS Seismic Angle	Bracing	13'-0"
5	129	H132-OS Uplift	Bracing	9'-8"
6	224	H132	Grid/Infill	3'-5"
7	224	H132	Grid/Infill	3'-10 3/8"
10	56	H132	Grid/Infill	4'-1 5/8"
334	1	H132	Wall Mount	7'-8 1/8"
337	1	H132	Wall Mount	68'-3 1/2"
361	1	H132	Wall Mount	84'-4 1/2"
20	1	H132	Wall Mount	242'-10 1/2"
365	1	H132	Wall Mount	250'-5 7/8"

Grand total: 1417


Exterior Stud Panels

Layout, Order, Build

- Panel creation
- QTO
- Benefits



Roof Area 2E2 QTO				
Area	Member	Count	Length	Total Length
Area 2E2 Roof	Steel Stud	100	9' - 2 7/8"	924' - 5"
Grand total:		100		924' - 5"
Area 2E2 Roof	Cold Rolled Steel Bridge	4	4' - 9 3/8"	19' - 1 3/4"
Area 2E2 Roof	Cold Rolled Steel Bridge	2	5' - 2 7/8"	10' - 5 7/8"
Area 2E2 Roof	Cold Rolled Steel Bridge	2	5' - 4 3/4"	10' - 9 3/8"
Area 2E2 Roof	Cold Rolled Steel Bridge	4	5' - 5 7/8"	21' - 11 3/4"
Area 2E2 Roof	Cold Rolled Steel Bridge	4	6' - 11 7/8"	27' - 11 3/4"
Area 2E2 Roof	Cold Rolled Steel Bridge	12	7' - 5 7/8"	89' - 11 1/8"
Area 2E2 Roof	Cold Rolled Steel Bridge	4	7' - 8 3/8"	30' - 9 3/4"
Area 2E2 Roof	Cold Rolled Steel Bridge	4	7' - 11 7/8"	31' - 11 3/4"
Grand total:		36		243' - 1"
Area 2E2 Roof	Steel Stud	4	4' - 9 1/2"	19' - 2"
Area 2E2 Roof	Steel Stud	8	5' - 6"	44' - 0"
Area 2E2 Roof	Steel Stud	4	7' - 0"	28' - 0"
Area 2E2 Roof	Steel Stud	12	7' - 6"	90' - 0"
Area 2E2 Roof	Steel Stud	4	7' - 8 1/2"	30' - 10"
Area 2E2 Roof	Steel Stud	4	8' - 0"	32' - 0"
Grand total:		36		244' - 0"



DATA CENTER

Roof Area 2D1-1

2D1-1

REVISION

NO.	DESCRIPTION	DATE
1	REVISION	

QUALITY CONTROL

NO.	DESCRIPTION	DATE
1	REVISION	


REVISION BLOCK

NO.	DESCRIPTION	DATE
1	REVISION	

QUALITY CONTROL

NO.	DESCRIPTION	DATE
1	REVISION	

Exterior Stud (Panel Sheet)



1 2D3307
3/8" = 1'-0"

Lbl	Qty	Member	Length (ft)
C0	6	SteelStud(400)	10' - 9"
T0	2	Steel Track (400)	7' - 4"
T1	2	Cold Rolled Steel Bridge	7' - 2 3/4"

NOTES

1. ALL TRACKS SET WITH 1/2" CLEARANCE TO BOTH SIDES OF STRUCTURAL STEEL
2. ALL STUDS HAVE 3/8" CLEARANCE FROM THE TOP OR TRACK
3. ALL BRIDGES SET AT 48" TO BE COLD ROLLED FASTENED TO STRUCTURAL STEEL AFTER INSTALL



2D1

ASSEMBLY INFORMATION

JOB NUMBER	
DESIGN	IFC
SYMBOLS BY	VPN
CALC BY	
POSTED BY	

6/14/2018 8:17:47 PM



2D3307

PANEL NUMBER


Interior Stud Wall Layout

Wall Preparation

- Wall layout drawing
- Rough opening layout
- Quality control



Interior Wall Layout (OVERALL)




Interior Stud Wall Penetrations

Box Outs

- Wall Layout Drawing
- Rough Opening Layout
- Quantity Takeoff



QTO for Area 1C						
Studs						
Sum of Length	Type					
Type of Wall		Corners	Infills	Kings	Cripples	Grand Total
Stud (600)		345	961	1740	243	3487
Stud (600s)		1805	10701	188	8455	24161
Grand Total		2150	11663	1928	8698	27648
Tracks						
Row Labels	Sum of Length					
Bottom Track	1284					
Header	831					
Top Track	1593					
Bridge	94					
Grand Total	3802					



2E1-Ground Floor 1/2
 1/4" = 1'-0"

QUALITY CONTROL

NO.	DATE	BY	CHECKED
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			
29			
30			
31			
32			
33			
34			
35			
36			
37			
38			
39			
40			
41			
42			
43			
44			
45			
46			
47			
48			
49			
50			
51			
52			
53			
54			
55			
56			
57			
58			
59			
60			
61			
62			
63			
64			
65			
66			
67			
68			
69			
70			
71			
72			
73			
74			
75			
76			
77			
78			
79			
80			
81			
82			
83			
84			
85			
86			
87			
88			
89			
90			
91			
92			
93			
94			
95			
96			
97			
98			
99			
100			

REVISION BLOCK

NO.	DATE	BY	REVISION
1			
2			
3			
4			
5			
6			
7			
8			
9			
10			
11			
12			
13			
14			
15			
16			
17			
18			
19			
20			
21			
22			
23			
24			
25			
26			
27			
28			

1B6sVB



END INDEX



2E1

ACKNOWLEDGMENTS

APPENDIX 3

REVIEW

9740.55 04

--	--

2022-03-01

18/2019 1:04:46 PM

Doors Frames & Hardware

Hardware Preinstall

- Stocking of material
- Build sheet
- Quality control





Prefab, Production Tracking & Quality Control

Assemble Systems

Analyze, condition, and share model-based building information to improve preconstruction and construction processes

Publish

- Access to BIM
- Import/Export to excel

Manage


- Model-Based Takeoff
- Estimating

Share

- Visualize Model data
- Organize by Color

iPad Online/Offline




Easy to use interface allows for quick grouping of similar scopes
Setup and filter multiple views to update data based on individual user needs



Parameter Creation

GROUPS

- Based on scopes of work
- Properties based on data to be tracked



Strut Prefabrication

Order ID

- Work package breakdown/Scheduling
- Organization of parts for cut optimization
- Tracking the build through Prefab Process
 - Packaging/Shipment/Delivery/Install
- Visualizing Percent complete using Power BI

Order ID Track				
Group by: Order ID Track				
	Name	Quantity	Unit	Projected Start
	▼ RVA2-E-001	530	EA	
	▶ 02/25/2019	530	EA	02/25/2019
	▼ RVA2-E-002	403	EA	
	▶ 03/21/2019	403	EA	03/21/2019
	▼ RVA2-E-003	319	EA	
	▶ 03/05/2019	319	EA	03/05/2019
	▼ RVA2-E-004	406	EA	
	▶ 03/30/2019	406	EA	03/30/2019
	▼ RVA2-E-005	330	EA	
	▶ 03/13/2019	330	EA	03/13/2019
	▼ RVA2-E-006	571	EA	
	▶ 04/11/2019	571	EA	04/11/2019

☒ Color objects by values of the property:

Strut Status

☐ Not Assigned

☒ Complete

☐ On-Site

☐ Ordered

☐ Palletized

Building 1

MDF A

Page: 1D_2

Stock Info

Qty: 2

Length: 20'

Cost: \$44.00

Usage, %: 82.71

Waste, %: 17.29

Offset Length: 3' 5 1/2"

Material/Type: H-132

Cuts Info

Cut No: 1 2 3 4

Cut Location: 4' 1 5/8" 8' 3 1/4" 12' 4 7/8" 16' 6 1/2"

Qty: 2

4' 1 5/8"	4' 1 5/8"	4' 1 5/8"	4' 1 5/8"	3' 5 1/2"
MDF - 15	MDF - 15	MDF - 15	MDF - 15	

Stock ID

Part ID

Length

Location

1

MDF - 15

4' 1 5/8"

4' 1 5/8"

1

MDF - 15

4' 1 5/8"

8' 3 1/4"

1

MDF - 15

4' 1 5/8"


12' 4 7/8"

1

MDF - 15

4' 1 5/8"

12' 4 7/8"




Framing and Inspection



Current Information

- Track multiple install and status completions
- Track inspections
- Work activity Dates, Issues, Notes
- Generate model based takeoffs
- Visualizing Percent complete using Power BI




Group by: Wall/Ceiling Tracking ▾		Columns	\$ Estimate	Import/Export ▾
<input type="checkbox"/>	Name	Quantity	Unit	
<input type="checkbox"/>	▼ Walls	62,420.90	SF	
<input type="checkbox"/>	▼ OF	20,589.27	SF	
<input type="checkbox"/>	▶ 1 side hung & finished	778.64	SF	
<input type="checkbox"/>	▶ 2 sides hung	491.76	SF	
<input type="checkbox"/>	▶ 2 sides hung & finished	18,276.21	SF	
<input type="checkbox"/>	▶ 2 sides hung, 1 side finished	651.93	SF	
<input type="checkbox"/>	▶ Not Assigned	390.74	SF	
<input type="checkbox"/>	▼ OG	19,068.66	SF	
<input type="checkbox"/>	▶ 2 sides hung & finished	17,582.32	SF	
<input type="checkbox"/>	▶ 2 sides hung, 1 side finished	829.93	SF	
<input type="checkbox"/>	▶ Framed	645.82	SF	
<input type="checkbox"/>	▶ Not Assigned	10.59	SF	
<input type="checkbox"/>	▼ OH	22,762.96	SF	
<input type="checkbox"/>	▶ 2 sides hung	205.15	SF	
<input type="checkbox"/>	▶ 2 sides hung & finished	21,768.80	SF	
<input type="checkbox"/>	▶ 2 sides hung, 1 side finished	652.50	SF	
<input type="checkbox"/>	▶ Framed	136.51	SF	
<input type="checkbox"/>	▼ Building 1	202,077.01	SF	
<input type="checkbox"/>	▼ Ceilings	662.00	SF	
<input type="checkbox"/>	▼ OG	594.86	SF	
<input type="checkbox"/>	▶ 1 side hung & finished	286.00	SF	
<input type="checkbox"/>	▶ 2 sides hung & finished	211.01	SF	
<input type="checkbox"/>	▶ Not Assigned	97.85	SF	
<input type="checkbox"/>	▼ 1B1	67.15	SF	


Door and Hardware Installation

Real Time Solutions

- Barcode scanning to quickly find the door you need
- Link Excel to assemble to create spreadsheets based on data
- Document, track, and share issues quickly and easily
- Inventory tracking



	Name	Quantity	Unit
<input type="checkbox"/>	▼ HM- Hollow Metal	204	EA
<input type="checkbox"/>	▶ Benchd	49	EA
<input type="checkbox"/>	▶ DDFD	21	EA
<input type="checkbox"/>	▶ Ordered	1	EA
<input type="checkbox"/>	▶ Shop	1	EA
<input type="checkbox"/>	▶ Site	83	EA
<input type="checkbox"/>	▶ Swinging	49	EA
<input type="checkbox"/>	▼ Horiz Rolling Gate	3	EA
<input type="checkbox"/>	▶ By Others	3	EA
<input type="checkbox"/>	▼ Roll Up	7	EA
<input type="checkbox"/>	▶ By Others	7	EA
<input type="checkbox"/>	▼ WD - Wood Door	29	EA
<input type="checkbox"/>	▶ Shop	29	EA
<input type="checkbox"/>	▼ 3	119	EA
<input type="checkbox"/>	▼ HM- Hollow Metal	114	EA
<input type="checkbox"/>	▶ Benchd	28	EA
<input type="checkbox"/>	▶ Ordered	2	EA
<input type="checkbox"/>	▶ Shop	73	EA
<input type="checkbox"/>	▶ Site	11	EA




Progress & Budget status




Power BI integration

- Publish to Power BI for completion % and budget tracking
- Data manipulation
- Cost & Trend analysis

Query Dependencies



SPW
Work In Place



Thank You!

To everyone for attending

