ES10337 COBie Implementation Case Study: Broward County Judicial Center

Rabi Sidawi, AIA

Senior AEC Solutions Consultant, Applied Software

Twitter: @rabisidawi





COBie Implementation Case Study: Broward County Judicial Center

A journey into the real world of COBie delivery.

The Broward County Judicial Center in Ft. Lauderdale, Florida, is a successful example of a commercial BIM remodeling project, delivering COBie both during the Design Phase at LOD 300, and at the end of Construction for LOD 500 as-builts.

You will learn about what were the challenges, solutions and opportunities, and takeaways for your next project.



At the end of this class, you will be able to:

- Take a journey into the real world of COBie delivery
- Learn about a successful example of a BIM remodeling project
- Compare COBie delivery for LOD 300 and LOD 500
- Understand challenges, solutions and opportunities








CHALLENGES: Owner-Defined Goals


- 1. Architect will work with the Owner to confirm selection of maintainable assets to be tracked and matured within the project.
- 2. Architect to verify that all components anticipated in the model exist and have valid naming.
- 3. Architect to verify that all components have a proper OmniClass Number/Title.
- 4. Develop the Data Requirement Schedule (mapping) to reverse engineer the fields required for FM deliverable by adding columns describing the COBie tabs, model component authors, data sources, and Revit parameters.





AUTODESK®

Information Exchanges Design



Served by **Described Operated** Constrained **Facilities** by by Composed by Building Systems of Models Product types Documents Floors Specifications Rooms/Spaces Components

LOD

- Input: Quantity & Accuracy of Information
- Output: Quality & Reliability of information

100 Estimate it

200 Specify it

300 Buy it

400 Build it . install it

500 Commission it . Operate it



BIM Uses

- Maintainable items
- Assets

Building (Preventative) Maintenance Scheduling

Building System Analysis
Asset Management
Space Management and Tracking

Disaster Planning

Record Modeling

Site Utilization Planning
Construction System Design
Digital Fabrication
3D Control and Planning

3D Coordination
Design Authoring
Engineering Analysis
Energy Analysis
Structural Analysis
Sustainability (LEED) Evaluation
Code Validation
Programming
Site Analysis
Design Reviews

Phase Planning (4D Modeling)
Cost Estimation


Existing Conditions Modeling



COMPONENT

Maintainable items

Assets







ABOUT COUNCILS & PROJECTS MEMBERSHIP RESOURCES **NEWS EVENTS** CONTACT

building SMARTalliance® a council of the National Institute of Building Sciences


Define the BIM Goals for the

Project

Describe the **BIM Uses**

Begin with the **End in Mind**











OK Carcel retr

FMS

OmniClass Table 13 & 23

now About COBie

Bill East YouTube

- COBie4Designers
- COBie4Owners
- **COBie4Contractors**


"COBie is the data information exchange of all managed and maintained assets in a building"

What is COBie?

CONSTRUCTION OPERATIONS BUILDING information exchange

						1
					12	
		8			1	
	3	7	2	100	3	
			3	100		
	3 .	5 -			4	
Bre (Petroline, Sale Westy, Alexandro St., Technolog 229470	Faul Daktery@GHL com	3014-07-30734-20-35	Metal Alementes 50 Thickness	001	Bre-Chilledon, Side-Metal, Alumonum 50, Thickness 239470	Automobile Parcel of
Bre-CF, Worklow Prantitional Abstracts 50, Thickness Life Fall	Find Calley@left com	2014-02-2011-0-20-05	Metal Abdraces to Thomas	THE R. L.	BYE-CP, Window, French Metal, Abstractors 50, Thailenna J39745	ductorine desir.
Big-CF Wrighter Change 50 Theorem (1951)	Faul Calcing@SSE core	2014-02-20714-23-65	50 Thickness	500	fire CF, Wrinking Obscure 50, Theologic 259513	Automak Revit d
Bre-CF Window Obsture 56 Thickness 239741	Ped Geley@GRE.com	2014-01-20714-20-35	50 Thickness	500	Bre-CF_Wirelew_Obscure:50_Trectmess:(33974)	Autodeol-Rept A
Big-Ormidae, Sale Ofetal, Alexandre St. Thebrane 200579	Four Calchygodols core	2014-00-20014-20-21	Matel Absorber 52 Thybono	5001. HOL	Bre-CPMINGLOV, Substituted Abstractors by Thurston, 2005 74	Autobod Savit A
BIR CF Window PartiAfrical Administration Theorem 201743	Faul Dakerghts N. con	2014-02-20154-23-33	Medal Alexander 90 Thismen	2003, 103	BIG CF Window French Midgle Abaronian SC Thabaron 200743	Andrews Street or
Sea-CF, Western Characte SO, Thickness (2996)4	Faul Oakley@495.com	3014-02-2011-4-20-35	50. Thickriess	001, 101	Bre-CP Window Obsoure-50 Theckness:239614	Autodick Rent A
ere-CF_Weston_Obscure.50_Thickness:129744	Fed. Datayorani.com	2014-02-20124-20-25	50 Thickrisis	000, 100	Bre-CF Window Obspure:00 Trackness:239744	Autobox Revit A
BIT-LFRINGER, Talk N/BITP, Alacterate IN, Thickness 2008-01	Fig. Clarkey (\$1841.100)	A014-00-JUNIA 30-81	Metal Absorber 92 Thisbeen	ORIG. 101, 201	Bre-CPWindow, Inde Afetal, Abstracus 63, 1816 perc 2 meas	SATURNA SHARE A
Sta-CF Western PauchMetal Alternation 55 Theatrest 255746	Fact Cathropists com	2014-02-20714-20-35	Metal Algebraies 52 Thirkness	000L 10L 001	Bre-CF Wireless Franch Martel Alamon as 52 Thursday 199748	Substitute Street of
Bra-CF Window Feed Metal Abandours 50 Thebress 324040	Faul Dakley@GRE.com	2014/03/20714 20:35	Metal Aluminum 50 Thickness	Dog	Bre-CP Window Freed Metal Akamenary-56 Thickness 234040	Autobox Says A
ble-CPRINGLY Windsty Abstracts to Thomas 20000	Faul Davie population		Metal Aluminum to Thickness	Det.	Bre-CPMIndow Inde-Metal Alamonan-55 Thukasoc 200045	Autobook Smit A
tre-Chimolony Selectivistal Alexandres 50 Thiologous 234542	Facil California (INC. com)		Metal Alemanas 50 Thickness	Dog .	Bre-Chinindow Side-Metal Aluminum 53 Thinkness 224042	Automobile Revit of
tre-CF Window Feed/Metal Alamonum 50 Thickness 124043	Fra.d. Christophilians, sorre	2014-00-20714-20-35	Maria Alexander-50 Thekreus	Bear.	Bre-CP Window Flood-Metal Abandours-SE Thickness 224043	Automobile Rept. A
BIR-CY WINDOW CRITICAL TO TRADERIC 23/8047	Paul Cathygows con	2014-00-20714-20-31	St Thiken	001.101	Bra-CP, Wordow, Obscuracióp, Photograp (1988)	Automobile Paul o
Bre-CF, Worker Obscure 50 Thistopic 224048	Paul Dalriey@rett com	2014-02-2013-8-20-05	SO Thickness	100%, 10%	Bre-CP, Wirelew Obscure:00, Physiness-224948	Autobia Brist J
Bre-CP Wireless Obscure 50 Thekness 234045	Fw.4. Oakleysh GNL nom	2014-02-20714-20-35	50 Thickness	001.101	Bre-CF Window Obscure:50 Thickness:214045	Autobok Revit /
ere-CP Written Chatters SC Trackress 224000	Park Datayoraks con	2014-00-20714-20-25	SO_Flackrises	004, 104	Bre-CF, Window, Obscure-So, Prickness JU4050	Autodow Revit A
Bre-CP Wireless PurchAfetal Abstracts 60 Thistony (2006)	Paul Galdeygotter com	2014-00-00714-20-01	Moral Absences to Thursday	000 L 100	Bre-CF, Wireless Flanck-Metal Abandous-100 Thehanos 204084	Autobio Navel o
Dep Chillington: Sale Siletal Alamanum-50 Thickness 234055	Faul Gebruch ONL man	2014-02-20114-20-33	Unital Alementes 50 Thickness	000, 100	See-Chillindole Side-Metal Alemenum 50 Thehmos 234085	Autodook Spot o
re-(Printing light Wirts) Aluminum-50 Thickness 234056	Faul Dahleyshilds com	3014-03-2071A-20-35	Moral Aluminum-52 Thickness	000L 100L	Bre-Charledon, Side-Metal Alicenses 50 Thickness 224056	Autodood Revit J
Bre-CP Window Feed Metal Abdresses NO Thickness 220057	Final Cable population some	2014-03-20714-20 85	Metal Aluminum 50 Thukness	0001, 1007	BIR-CF Wirelow Flord Metal Abstracts 50 15 skney; 334057	Autobrok Bayd A
Bre-CF Wireless Obscure 50 The Avenue [1] 4001	Faid California State com	2014-02-20714-20-95	50 Thickwise	00L 103	Bre-CP Window Obscure:50 Thickness-(2)4061	Autobok Spot A
Ine-CF Window Obscure-SE Thickness: 234062	Faut Gerlyspield, tory	3014-02-2071-9-20-25	50 Pactretti	00L 101	Bre-CP Window Obsours:50 Thickness:224062	Autobox Auvit A
BIE-CF William Chappie Sc Transpers 22 8763	Paul Dakwygrami.com	2014-00-20710-20-35		001, 101	BIR-CP Window Obstage-OD Thickness-338063	Subspieck Naviet A
No.CF Weslew Channello Thelings 224064	Faul California 955 com	2014-03-2073-4-20-35		000, 100	Bre-CF Wirelew Obsoure:50 Thirkness-224064	Autorioù Sayet J
Dra-CP Window FlandSvietal Aluminum-50 Thickness (2406)	Faul Dakteyshild Com		Oletal Aluminum-53 Thickness	000, 100, 201	Bra-CP Window Fleed-Metal Aluminum 50 Thickness 224068	Autodick Revit A
FIR-CPRINGING SIZE DAVIS ALLEGACIE-50 TECKNESS 234009	Paul Carriero with corn		Metal Aluminum 52 Thatesan	000, 101, 201	Bre-CFWindow Inde/Annual Aluminum-50 Thickness 224069	ALTORNA RIVE I
Fre-CPRINGERS SAIR SURFAL Allerences NO. Thomasso 224070	Park Control (1997-2009)		Motal Abrevant 90 Thekens	000, 100, 201	for CPRIndow Inde-Motal Alamonaes 92 Thickneys 224075	Autobios Book A
tre-CF Window Fleed/Metal Aluminum-50 Thickness 224071	Two Dakley British core	and the second second second second second	Metal Alexander 50 Theleson	001, 101, 201	Bre-CP Wireless Flood-Metal Aluminum-50 Thickness 224071	Autodool Savit
ere-CF Writine Fined Switze Aluminum-50 Thickness 225642	Fix.d Clarkey@GRE.com	And the second second second	Metal Aluminum-50 Thickness	Des	Bre-CF Window Feed Metal Aluminum-50 Thickness 225622	Autodox Revit A
the CPRINGER Sale Welg Aleranovito Thairesc 229453	Faul Daviey@est.icm	and the second second second second	Motal Alamerant to Thuleson	bec	Bre-CPWindow Mile-Metal Aluminum-90 Thisbness-228663	Exhadent Next a
Bre-CFillington Sele-Metal Alemanum 30 Teckness 225634	Facil Oakley@SNE.com		Westerl Altertrains 50 Thickness	lbes .	Bre-Chilledole Schribbral Alamonam-50 Thickness 225634	Automobile Square
THE RESERVE TO SECURE ASSESSMENT AND ADDRESS.	coor Zore Type	WELL AND ROWS IN SIX SER.	Marriedy Cores	POS.	A STATE OF THE RESIDENCE OF THE RESIDENC	Street, Square, Square

Things Should Know About COBie





now About COBie

Design

- Contact
- Facility
- Floor
- Space
- Zone
- Type
- Component
- System
- Assembly
- Connection
- Resource
- Job
- Impact
- Document
- Attribute
- Coordinate
- Issue

Build

- Contact
- Facility
- Floor
- Space
- Zone
- Type
- Component
- System
- Assembly
- Connection
- Resource
- Job
- Impact
- Document
- Attribute
- Coordinate
- Issue

Operate

- Contact
- Facility
- Floor
- Space
- Zone
- Type
- Component
- System
- Assembly
- Connection
- Resource
- Job
- Impact
- Document
- Attribute
- Coordinate
- Issue










BCJC BIMLink-COBie mapping

BIM Planning Element	Current Level	Target Level	Total Possible		
Strategy	9	21	25		
Organizational Mission and Goals	2	4	5		
BIM Vision and Objectives	2	4	5		
Management Support	2	4	5		
BIM Champion	1	5	5		
BIM Planning Committee	2	4	5		
BIM Uses	3	8	10		
Project Uses	2	5	5		
Operational Uses	1	3	5		
Process	2	7	10		
Project Processes	1	4	5		
Organizational Processes	1	3	5		
Information	2	12	15		
Model Element Breakdown (MEB)	1	4	5		
Level of Development (LOD)	1	4	5		
Facility Data	0	4	5		
Infrastructure	7	11	15		
Software	4	5	5		
Hardware	2	3	5		
Physical Spaces	1	3	5		
Personnel	10	20	25		
Roles and Responsibilities	2	4	5		
Organizational Hierarchy	2	4	5		
Education	2	4	5		
Training	2	4	5		
Change Readiness	2	4	5		
Totals	33	79	100		





AUTODESK_®

 PROJECT OWNER : BROWARD COUNTY

PROJECT NAME : BROWARD COUNTY JUDICIAL COMPLEX MIDRISE FULL BUILDING RENOVATION

PROJECT ADDRESS : 540 S.E. 3RD AVENUE, FORT LAUDERDALE, FL 33301

CONTRACT TYPE : LUMP SUM

BRIEF PROJECT DESCRIPTION: FULL INTERIOR RENOVATION & CONSTRUCTION FIT OUT (ALL FOUR FLOORS)

EMAIL ID

OF THE EXISTING MIDRISE BUILDING

PROJECT NUMBER : 060-2013-001(SA - Project Number) & RLI M1102907R1 (BC Number)

SECTION C: KEY PROJECT CONTACTS

OPCANIZATION CONTACT NAME DOLE

ORGANIZATION	CONTACT NAME	ROLE	EMAIL ID	PHONE #
• BC	Rob Dennis	Project Manager	rodennis@broward.org	954-357-64
BC	Brian Kraus	Facilities Maint.	bkraus@broward.org	954-357-53
SA	Chirag Thaker	President	chirag.thaker@rdaep.com	954-537-91
•SA	Albino Rios	Project Manager	albino rios@rdaen.com	954-537-91
SA	Hernan Pagan	BIM Coordinator	hernan.pagan@rdaep.com	954-537-91
S&F	Sri Sritharan	Principal	sri@sfengineers.com	954-938-002
•S&F	Donata Williams	Project Manager	donata@sfengineers.com	954-938-002
S&F	Laura Sotomayor	BIM Coordinator	laura@sfengineers.com	954-938-002
FE	Keith Mote	Project Engineer	kmote@flynnengineering.com	954-522-100
AA	Brian Kitchens	Project Manager	bkitchens@archall.net	954-764-88!
SG	Jonathan Burges	LEED Project Manager	jonathan@thespinnakergroupinc.com	754-800-310
SG	Jessica Stanley	LEED Project Manager	jessica@thespinnakergroupinc.com	954-366-827
DG	George San Juan	Principal	geanjuan@doltag.not	954-527-11:
•DG	Steeve Robitaille	HVAC / MEP Project Manager	steeve@deltag.net	954-527-11:
טט	Jorge Banamonde	Fire Protection	JorgeB@deltag.net	954-527-11:
DG	Igor Loncarevic	Plumbing	igor@deltag.net	954-527-11:
1	Jormaino Williams		jamaina@daltag.nat	954-527-11:
ASTI	Rabi Sidawi	COBie Consultant	rsidawi@asti.com	404-564-18
PC / GC	Gary Pirtie	vice President	gary@pirtleconstruction.com	954-343-60!
•PC / GC	Jeff Miles	Director of ops.	jeff@pirtleconstruction.com	954-343-540
PC	Elaine Choe	BIM Coordinator	Elaine@pirtleconstruction.com	954-343-60!
	• BC BC SA •SA •SA •S&F •S&F FE AA SG DG DG DG DG DG PC/GC •PC/GC	BC Brian Kraus SA Chirag Thaker SA Albino Rios SA Hernan Pagan S&F Sri Sritnaran S&F Donata Williams S&F Laura Sotomayor FE Keith Mote AA Brian Kitchens SG Jonathan Burges SG Jessica Stanley DG George San Juan DG Steeve Robitaille DG Jorge Banamonde DG Igor Loncarevic DG Jorge Banamonde DG Igor Loncarevic DG Jorge Banamonde	BC Rob Dennis Project Manager BC Brian Kraus Facilities Maint. SA Chirag Thaker President SA Albino Rios Project Manager SA Hernan Pagan BIM Coordinator S&F STI STITTMATAN PRINCIPAL S&F Donata Williams Project Manager S&F Laura Sotomayor BIM Coordinator FE Keith Mote Project Engineer AA Brian Kitchens Project Manager SG Jonathan Burges LEED Project Manager SG Jessica Stanley LEED Project Manager DG George San Juan Principal DG Steeve Robitaille HVAC / MEP Project Manager DG Jorge Banamonde Fire Protection DG Igor Loncarevic Plumbing DG Jorge Banamonde Fire Protection DG Igor Loncarevic Plumbing DG Jorge Banamonde Consultant PC / GC Gary Pirtle Vice President PC / GC Jeff Miles Director of ops.	BC Brian Kraus Facilities Maint. bkraus@broward.org SA Chirag Thaker President chirag.thaker@rdaep.com SA Albino Rios Project Manager SA Hernan Pagan BIM Coordinator S&F STITINATAN Principal STI@stengineers.com S&F Donata Williams Project Manager S&F Laura Sotomayor BIM Coordinator laura@sfengineers.com FE Keith Mote Project Engineer kmote@flynnengineering.com AA Brian Kitchens Project Manager bkitchens@archall.net SG Jessica Stanley LEED Project Manager SG Jessica Stanley LEED Project Manager DG George San Juan Principal grapius@deltag.net DG Steeve Robitaille HVAC / MEP Project Manager DG Jorge Banamonde Pile Project Manager DG

BIM EXECUTION PLAN

VERSION 3.0 FOR

BROWARD COUNTY JUDICIAL COMPLEX MIDRISE FULL BUILDING RENOVATION







SINGER ARCHITECTS

915 MIDDLE RIVER DRIVE. SUITE 404 FORT LAUDERDALE, FLORIDA 33304 TEL. 954-537-9136





S&F Engineers, Inc. 2925 W. Cypress Creek Rd., ste. 200 Fort Lauderdale, Florida 33309 p:954.938.0020 f:954.938.0468 e:sfe@sfengineers.com C.A.# 8852

BROWARD COUNTY JUDICIAL COMPLEX MIDRISE FULL BUILDING RENOVATION

CONTENT:

SECTION A BIM PROJECT EXECUTION PLAN OVERVIEW

SECTION B PROJECT INFORMATION

SECTION C KEY PROJECT CONTACTS

SECTION D PROJECT GOALS / BIM USES

SECTION E ORGANIZATIONAL ROLES / STAFFING

SECTION F BIM PROCESS DESIGN

SECTION G BIM AND FACILITY DATA REQUIREMENTS

SECTION H COLLABORATION PROCEDURES

SECTION I QUALITY CONTROL

SECTION J TECHNOLOGICAL INFRASTRUCTURE NEEDS

SECTION K MODEL STRUCTURE

SECTION L PROJECT DELIVERABLES

SECTION M REVIT MODEL OWNERSHIP & COBIE RESPONSIBILITY SEQUENCE/ STRATEGY

SECTION N BIM ROLES AND RESPONSIBLITIES DURING CONSTRUCTION

SECTION O ATTACHMENTS

SECTION P GLOSSARY

What Assets to Track?

- 1. Project Info
- 2. Levels
- 3. Rooms
- 4. Light Fixtures
- 5. Mechanical Equipment
- 6. Electrical Equipment
- 7. Specialty Equipment
- 8. Floors
- 9. Roofs
- 10. Electrical Fixtures
- 11. Lighting Devices
- 12. Plumbing Fixtures

BROWARD COUNTY JUDICIAL COMPLEX MIDRISE FULL BUILDING RENOVATION

ORGANIZATION DETAILSa

SA – Singer Architects (Architecture) S&F – S & F Engineering (Structure) PC - Pirtle Construction

FE – Flynn Engineering (Civil) SG – Spinnaker Group (LEED Consulting)

DG – Delta G Consulting Engineers (MEP) ASTI – Applied Software (COBIE Consultant)

SECTION D: PROJECT GOALS / BIM USES

ORGANIZATION	USES
SA	Design Authoring, Design Coordination, Drawing Production, Clash Detection & COBie implementation Asset Management, Design Reviews, Space Management & Tracking, Record Modeling, Code Validation, Programming, Design Reviews, Existing Conditions Modeling.
S&F	Design Authoring, Code Validation Design Reviews, Design Coordination, Drawing Production & Clash Detection, Engineering Analysis, Structural Analysis
FE	Drawing Production, Design Reviews
DG	Design Authoring, Design Coordination, Drawing Production, Clash Detection (MEP specific) & COBie implementation, Space Management and Tracking, Engineering Analysis, Code Validation, Programming, Design Reviews, Existing Conditions Modeling.
PC	To be determined by Construction team.

Clash Detection Schedule

Internal Periodic Clash Detection sessions to be held within each phase as needed for coordination between all teams:

To occur as detailed below:

- 100% Schematic Design & Design Development Phase
- 50% Construction Documentation Phase
- Before 100% Construction Documents are issued
- 100% CD
- Bidding/ Permitting

Clash Detection Meeting

- Typically, meetings will be internal coordination sessions between the A/E design & project team.
- Construction team's (GC) attendance, up to permitting phase, is welcome but not mandatory.
- If the County's involvement is needed to resolve any issues, a notification will be provided to the owner for follow up meetings or input.
- Each discipline must submit a clean *.RVT file minimum 3 days before the meeting.





SECTION G: BIM AND FACILITY DATA (COBie) REQUIREMENTS

Refer to attachment:

- 1. "BCJC BIM Component COBie Checklist Omniclass Table 23".
- "BCJC COBie Model Component Author" (Attachment A) for a phase by phase description of COBie items and the responsibilities of each team member.

SECTION H: COLLABORATION PROCESS

Meeting Procedure


MEETING TYPE	PROJECT STAGE	PARTICIPANT	FREQUENCY	LOCATION
KICK-OFF	Notice to Proceed	Entire Project Team	Once	COUNTY GOV.CNTR
DESIGN COORDINATION	Pre Design/DD/CD	Team Leaders	Weekly	Conference Call
BIM MEETINGS	Pre Design/DD/CD	BIM Managers	Weekly / As required	Conference Call

Note - BIM meetings mainly involve the participation of BIM Managers & Project Managers for coordination. However, the County & other interested parties may join if requested and a physical meeting can be scheduled accordingly and if required.

Model Delivery Schedule (Revit and CAD)

INFORMATION EXCHANGE	DESIGN TEAM	FREQUENCY	DUE DATE	NATIVE FILE TYPE
DESIGN AUTHORING	Architect	Weekly	Friday (By 5 PM)	.RVT & PDF
	Structural Engineer	As Requested & Based on Development		.RVT & PDF
	MEP-FP Engineer	Weekly	Friday (By 5 PM)	.RVT & PDF
	Civil Engineer	As Requested & Based on Development		.DWG
	Landscape Architect	As Requested & Based on Development		.DWG





LOD Definitions

Based on Government Services Administration (GSA) Standards

LOD 100

Overall building massing indicative area, height, volume, location, and orientation may be modeled in three dimensions or represented by other data.

The Model Element may be graphically represented in the Model with a symbol or other generic representation, but does not satisfy the requirements for LOD 200. Information related to the Model Element (i.e. cost per square foot, tonnage of HVAC, etc.) can be derived from other Model Elements.

LOD 200

Model elements are modeled as generalized systems or assemblies with approximate quantities, size, shape, location, and orientation. Non-geometric information may also be attached to Model Elements. Partitions and furniture models shall be included in this phase.

LOD 300

Model Elements are modeled as specific assemblies accurate in terms of quantity, size, shape, location, and orientation. Non-geometric information may also be attached to Model Elements and equivalent to 100% construction documents.

LOD 300 (MEP)

Modeled as design-specified size, shape, spacing, and location of fixtures, equipment, pipe, valves, fittings, and insulation for risers, mains, and branches; approximate allowances for spacing and clearances required for all specified anchors, supports, vibration and seismic control that are utilized in the layout of equipment; actual access/code clearance requirements modeled and equivalent to 100% construction documents.



Facilities Maintenance	Broward County	Revit, AiM,	2014-2015
Coordination		AssetWorks	
COBie Implementation	Broward County	AiM, AssetWorks	2015
Construction Management/ COBie	GC	Revit	2015
3D Coordination / Clash Detection	ALL	Navisworks Manage	2014-2015
COBIE Export	ALL	COBie Extension	2014-2015
		Revit add-in	
Construction Administration (RFIs	ALL	BIM 360 Glue &	2015
etc)		Field	

All Revit models will be converted to Revit 2015 at the end of permitting phase.

SECTION K: MODEL STRUCTURE

FILE NAMING CONVENTION	
ProjectNumber_Discipline_Central_Version.RVT	(Should a file be upgraded to another version of Revit, the
	original name will remain as is, in order to preserve links &
	file references.)
Architecture Model	0602013001_ARCH_CENTRAL_2014.RVT
Furniture Model	0602013001_FURN_CENTRAL_2014.RVT
Structure Model	0602013001_STRUC_CENTRAL_2014.RVT
Mechanical Model (HVAC)	0602013001_MECH_CENTRAL_2014.RVT
Electrical Model	0602013001_ELEC_CENTRAL_2014.RVT
Plumbing Model	0602013001_PLUM_CENTRAL_2014.RVT
Fire Protection Model	0602013001_FIRE PROTECTION_CENTRAL_2014.RVT
LOD 350/400/500 models	TBD BY GC


Project Units

The model unit system is Imperial

Tolerance in Revit will be set to 1/16" and the dimension styles will round to the appropriate increment depending on the scale.



SECTION M: REVIT MODEL OWNERSHIP & COBIE RESPONSIBILITY SEQUENCE/ STRATEGY





Construction Phase Guidelines

- 1. Model Sharing
- 2. LOD can vary by element
- Mandate BIM 360 Glue and BIM 360 Field
- 4. Prequalify Subcontractors based on BIM Proficiency
- 5. Supplemental Instructions shall be incorporated into the BIM models
- 6. Coordination meetings
- 7. COBie delivery
- 8. Record vs. As-built models

- Latest Revit models shall be provided to the GC after permits are approved and at issuance of NTP1 to GC, for development of the LOD 350/400/500 models (shop drawings) as defined by BIM forum and as required by County.
- Not all items may need to be developed to LOD 350/400. GC shall coordinate with County and develop MEP-FP, Architectural & Structural items to LOD level required for each discipline as directed by County.
- Once construction begins, the GC shall be responsible for all LOD 350/400/500 Revit model developments and any changes to COBie data based on field verification, constructability, final product selection & installation.
- The GC shall use BIM 360 Field & Glue for the gathering of COBie field data from Construction Manager/ Superintendent and all sub-contractors in order to integrate all information into the BIM models throughout construction.
- 8. GC shall review subcontractors BIM proficiency and qualifications.
- For instances where drawing modifications are required from A/E team to provide sketches, Supplemental Instructions, etc. This information shall be implemented into the Revit models via use of BIM 360 Field & Glue Collaboration. The A/E team will also submit PDFs of all changes to the GC.
- 10. Construction team (GC) shall be responsible to provide a location and access for the upload/ download of the latest Revit models by A/E teams / sub-contractors to add information, answer RFI's, etc. Construction team (GC) shall keep daily backups of all models Should the GC give ownership of the same model to multiple subcontractors, the GC shall be responsible for organizing and merging all new information into one model including but not limited to: shop drawing sheets, views, updated Revit components, COBie information, etc.
- The construction team shall schedule virtual coordination meetings as necessary for coordination with Owner and/or A/E team.
- At the end of construction phase, the GC shall provide COBie deliverables to the Owner for Facilities Maintenance (FM)/ Operations & Maintenance (O&M) as required by the County.
- At the end of construction phase, the GC shall provide as-built full size drawings and PDFs and transfer the latest Revit models to the A/E team for Review.
- 14. The A/E team will review as-built information relevant to the development of record drawings and produce a record model & PDFs for delivery to owner.
- The GC shall also deliver a construction model (LOD 350, 400, 500) to the Owner for FM / O&M use at end of construction.



COBie Process

- Confirm selection of maintainable assets to be tracked and matured within the project.
- 2. Verify that all components anticipated in the model exist and have valid naming.
- 3. Verify that all components have a proper OmniClass Number and Title.
- Provide Level of Development (LOD) per model component author (MCA) and project phase coordinated with each component and space Object via OmniClass
- 5. Export spreadsheet to stakeholders
- 6. Import stakeholder spreadsheets to BIMLink
- 7. Single category export to BIMLink, map Sheet to COBie Template TAB

BIM-COBie Best practices

- Assign the proper Revit Category to each component
- Assign the proper Component Family Name and Type Name
- Eliminate the use of Revit in-place families
- Minimize the use of Model Groups

COBie Workflow

- 1. Populating the BIM Component Checklist
- Identify Revit Categories and Family Types to be tracked
- 3. Map Revit data to COBie spreadsheet tabs
- 4. Assign OmniClass table 23 codes to component and system families
- 5. Assign OmniClass table 13 space types to rooms
- 6. Create & Maintain BIMLink Links for Exporting Revit data to Excel Spreadsheets
- 7. Edit/Add information to the Excel spreadsheets
- 8. Import, Update & Export COBie data to/from Revit via BIMLink to Excel
- Map BIMLink data to COBie spreadsheet tabs




Conclusion

Family component level of development is appropriate for 100% SD Phase Omniclass COBie design data exists for most model elements identified in the BIM Component Check List, as approved by the owner.

The BIM Component Checklist which is represented in the **COBie2-ComponentsToSchedule** is NOT utilized in this phase. This issue remains to be discussed, as it may be substituted by another tool.

We have found some Revit families in the BIM with no family category, unidentified family name or type name. Groups have improved greatly especially in regards to system furniture. Some Revit families and materials have unassigned Uniformat Assembly Codes and most have unassigned OmniClass codes. Some elements do not have an associated material or are not associated with a manufacturer. In the case of Rooms, we have found that some rooms are unplaced, or redundant. Some rooms have invalid volume information, ceiling heights not defined, planned area, associated floor finish, style, department or occupancy. Modeling for Existing conditions has improved. The inability of Revit to schedule "groups" has been replaced by the use of "placeholder" families to schedule system furniture cubicle types, is a great improvement.

- 0602013011_ARCH_CENTRAL_2014.RVT
- 0602013011_STRUC_CENTRAL_2014.RVT
- 0602013011_MECH_CENTRAL_2014.RVT
- 0602013011_ELEC_CENTRAL_2014.RVT
- 0602013011_PLUM_CENTRAL_2014.RVT
- 0602013011_FIREPROTECTION_CENTRAL_2014.RVT
- 0602013011_FURN_CENTRAL_2014.RVT






LOD 200. Generate cost estimates based on assemblies

LOD 250. Define CSI Master-Spec Material classification


LOD 250. Generate cost estimates to be based on count and material take-offs

LOD 300. Define Omniclass Classification for Asset Tracking



BIM Proficiencies

BIM Proficiency Score



A - Physical Accuracy of Model	2.5
B- IPD Methodology	1.5
C - Calculation Mentality	1
D - Location Awareness	2
E - Content Creation	2
F - Construction Data	1
G - As-Built Modeling	0
H- FM Data Richness	1


Max Score of 4 at each	11

Figure 1 – BCJC BIM Proficiency Diagram at 100% SD Phase BIM Peer Review

Figure 2 - BCJC BIM Proficiency Score



The second secon	desk: works		ash Re	Tolerance	Clashes 62	1000	tive Revi	lewed	Approv	ed Resolve	ed Type S	POST-PROPERTY.					
lmage	Clash Nar	me Statu	s Distance	Grid Locati		02	Date F	Found		Item ID	[FIGURA]	Item	1 y Name	Element Ty	ype Item ID	lter Category	n 2 Name Element Type
*	Clash1	New	-0.48	D.2-5 : FOU	INDATIC	ON PLAN	2014/	5/16 1	3:57.12	Element	ID: 26198	7 Structur	ral Framing	;W16X36	Element ID: 84234	Ducts	Taps / Short Radius
7	Clash2	New	-0.47	F-9.2 : FOU	INDATIO	N PLAN	2014/	5/16 1	3:57.12	Element	ID: 26877	1 Structur	ral Framing	;W16X26	Element ID: 91180	5 Ducts	Taps / Short Radius



BCJC Clash Detection Matrix	NO. OF CLASHES - MHT REPORTS										
Clash Detection Results - by Category	28.05.2014	29.05.2014	04.06.2014	09.06.2014	10.06.2014	12.06.2014	17.06.2014	19.06.2014			
MECH vs. ELEC_LIGHT FIXTURES_PANELS_EQUIP	101	97	9	5	93	93	5	5			
MECH vs. ARCH_CEILINGS	464	490	489	276	436	136	137	137			
MECH+PLUM vs. ELEC	101	99	9	5	95	95	6	6			



BIM Peer Review @ 100% SD's

Autodesk BIM 360 Glue

lization











Recommendations on corrective strategies

Care should be taken to avoid the following practices:

- 1. Linking unnecessary CAD files (FP, Mech, Plum, Arch)
- 2. Rooms without valid boundaries
- 3. Room names with lower case Text
- 4. Duplicate Elements (such as Structural elements, Doors, Plumbing Fixtures, Furniture, etc.)
- 5. Components without an OmniClass classification
- 6. Components not associated with a room
- 7. Use of Generic Models

Sample Revit Schedules showing areas where improvement can be made


Plumbing Fixtures	.					
3RD FLOOR	Plumbing Fixtures					
3RD FLOOR	Plumbing Fixtures			23.45.55.21	Drains (Wastes	
3RD FLOOR	Plumbing Fixtures			23.45.55.21	Drains (Wastes	
3RD FLOOR	Plumbing Fixtures			23.45.55.21	Drains (Wastes	
3RD FLOOR	Plumbing Fixtures			23.45.55.21	Drains (Wastes	
3RD FLOOR	Plumbing Fixtures			23.45.00.00	Sanitary, Laund	
3RD FLOOR	Plumbing Fixtures	D2010310	Lavatories - Single	23.45.05.14.14	Sinks/Lavatoric	
3RD FLOOR	Plumbing Fixtures	D2010310	Lavatories - Single	23.45.05.14.14	Sinks/Lavatoria	
3RD FLOOR	Plumbing Fixtures	D2010110	Water Closets - Single	23.45.05.21.11.	Water Operated	
3RD FLOOR	Plumbing Fixtures	D2040410	water Closets - Single	23.45.05.21.11.	Walter Operated	
3RD FLOOR	Flumbing Fixtures					
3RD FLOOR	Plumbing Fixtures					
3RD FLOOR	Plumbing Extures					
Plumbing Fixtures	i: 1					
Security Devices						
3RD FLOOR	Security Devices			23.85.30.11.11	Access Control	
3RD FLOOR	Security Devices			23.85.30.11.11	Access Control	

Α	В	С	D	E	F	G	Н
		Uni	format	Omni	Class	F	Room
Level	Category	Assembly Code	Assembly Descripti	OmniClass Nu	OmniClass Tit	Room: Num	Room: Name
Generic Models							
	Generic Models						
/	Generic Models						
Generic Models 8							
Lighting Fixtures			\		/		
\	Lighting Fixtures						
	Lighting Fixtures						
Lighting Fixtures: 12							
Casework							
1ST FLOOR T.	Casework	C1030400	Fabricated Cabinets &	23.40.35.17.47.	Kitchen Casew		
1ST FLOOR T.	Casework	C1030410	Cabinets	23.40.35.17.47.	Kitchen Casew	1408	BREAK RM

Air Terminals									
4TH FLOOR	Air Terminals		23.75.70.21.27.	Diffusers, Regis				787	Exhaust Diffuser
4TH FLOOR	Air Terminals		26.75.70.21.27.	Diffusers, Regis				788	Exhaust Diffuser
4TH FLOOR	Air Terminals		/		4445	ENTRY	Default	910	Non_Hosted-Line
4TH FLOOR	Air Terminals				4445	ENTRY	Defaut	911	Non_Hosted-Lines
4TH FLOOR	Air Terminals	/			4443	E-FILING	Default	912	Non_Hosted-Lines
4TH FLOOR	Air Terminals	T			4443	E-FILING	Default	913	Non_Hosted-Linea
4TH FLOOR	Air Terminais				4443	E-FILING	Default	914	Non_Hosted-Line
4TH FLOOR	Air Terminals				4443	E-FILING	Default	915	Non_Hosted-Lines
4TH FLOOR	Air Terminals	· · · · · · · · · · · · · · · · · · ·	İ		4436	MEETING RM	Default	916	Non_Hosted-Linea
4TH FLOOR	Air Terminais				4436	MEETING RM	Defaut	917	Non_Hosted-Line
4TH FLOOR	Air Terminals				4435	MEETING RM	Default	918	Non_Hosted-Lines
4TH FLOOR	Air Terminals				4435	MEETING RM	Default	919	Non_Hosted-Linea
4TH FLOOR	Air Terminais				4443	E-FILING	Default	936	Non_Hosted-Line
4TH FLOOR	Air Terminals			1/	4443	E-FILING	Default	937	Non_Hosted-Lines
4TH FLOOR	Air Terminals			/	4436	MEETING RM	Default	939	Non_Hosted-Linea
4TH FLOOR	Air Terminais			/	4435	MEETING RM	Default	940	Non_Hosted-Line
4TH FLOOR	Air Terminals		73.75.70.21.27	Diffusers, Regis				C	Return Diffuser -
4TH FLOOR	Air Terminals		23 75.70.21 27.	Diffusers, Regis				С	Return Diffuser -



COBIG 2.4 For Autodesk Revit



Rendering Settings	Edit
Locked Orientation	
Perspective	
Eye Elevation	132' 9 33/128"
Татт целации	27' 8 23/256"
Camera Position	Adjusting
Phasing	
Phase Filter	Show Complete
Phase	New Construction
Other	
Sheet Discipline #	
Properties help	

COBIE EXPORT SETUP INSTRUCTIONS

Before you Start

- Detach & Save as Central File
- Create a 3D View
- Merge Phase 2 & 3 (Use combine with next)
- Merge Phase Existing & Phase 1 (Use combine with previous)

COBie Extension Contacts

- Import Contacts from XML
- Change contact information
- Export as XML File
- Save & Close

COBie Extension Settings

- Import Settings from XML
- Check "United States" Check "Global Unique Identifier (GUID)"
- Uncheck "append Arch or MEP to each"
- "Component in system" checkbox must be checked or file will be
- invalid-"Each component listed in its own row"
- Mark element ID./Family _Type_Type Mark
- Check items to track by Room or Spaces
- Check all applicable items to track
- Save & Export Settings to XML File

COBie Extension Modify

- Select elements to be exported
- Select: 'Ungroup & set parameter'
- Batch modify other fields to be exported
- Ungroup and set parameters
- Select to update "all" parameters (first run)
- Select "Blank" or "all" if any items updated
- Export & Uncheck coordinates




Autodesk Building Solutions YouTube

COBie Toolkit for Autodesk Revit

Rich Mitrenga T.J. Meehan







About COBie

Learn the basics about the COBie data exchange standard, including information about deliverables and the overall worksheet structure.

Learn More »



COBie with Revit

Discover how specific Autodesk Revit features align with the COBie data exchange format and what considerations should be made prior to exporting data from a model.

Learn More »




Documentation

Procedurally outlines how to setup, configure, utilize, and export COBie data from Revit Models using the COBie Extension for Autodesk Revit.


Learn More »







AUTODESK.




Spaces :


Select Room for all

COBie Extension | Default Settings

Site Pads

Specialty Equipmer Sprinklers Stair Landings





General

- Use COBie 2.4 formatted spreadsheet
- Use the BIM Project Execution Plan (PxP)
- Does NOT import data back into Revit
- Does NOT read linked files
- Does NOT work with Design Options
- Does NOT work with Phasing
- Integration with Broward County FM System: What FM System does Broward County use (Assetworks AiM)?
- Is AiM compatible with COBie 2.4?
- Owner's Expectations for COBie: Track Assets for O&M

BCJC

- BIM Uses defined by Broward County
- Model Component Author (MCA)
- Who will lead each discipline?
- Transfer Data Custodian role from Singer Architects to Pirtle Const. for at 100% CD
- Early Participation of all stakeholders
- Pirtle Construction role in COBie
 - Do you have a BIM/COBie process?
 - Will there be another as-built model LOD 400-500?
 - What data will be gathered and tracked?
 - How will data embed into as-built model?
- Delta-G 's role (MEP Engineer)


Best Practices


- Delete redundant rooms and spaces
- Do not export to COBie coordinates tab
- Do not append (_MEP) to space names
- Attribute tab contain the custom parameters
- Do not use COBie zones & system tabs











- Via the Survey Stations, email or mobile device.
- AU 2016 passes awarded daily!
- Give your feedback after each session.
- Give instructors feedback in real-time.





After AU visit: Autodesk University.com

Click on My AU to find:

- Class Recordings
- Presentations
- Handouts

All of your sessions will be there to enjoy again and again.



Seek answers to all of your technical product questions by visiting the Answer Bar.

- Open daily 8am-10am and Noon-6pm and located just outside of Hall C on Level 2.
- Staffed by Autodesk developers, QA, & support engineers ready to help you through your most challenging technical questions.





